

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	6-01009-0000		6-01009-0100
				90% FED 10% ST	90% FED 10% ST	90% FED 10% ST
				ROADWAY	BRIDGE	ROADWAY
				0013	0013	0013
				084-0171	084-0171	RURAL
70300150	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	2,059	2,059		
70300900	PAVEMENT MARKING TAPE, TYPE IV - LETTERS AND SYMBOLS	SQ FT	63	63		
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	12,352	12,352		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	825.0	825.0		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,325.0	1,325.0		
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	4		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	18	18		
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	9	9		
* 72501000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	28	28		
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	312	312		
* 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	131	131		
* 78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	68	68		

\* SPECIALTY ITEM

△ REV. 10-28-2019 REV. - MS

**TRAFFIC BARRIER TERMINAL, TYPE 6**

FROM STATION	TO STATION	LT/RT	EACH
48+27.46	48+66.86	RT	1
51+39.39	51+78.79	LT	1
TOTAL			2

**TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT**

FROM STATION	TO STATION	LT/RT	EACH
47+77.47	48+27.46	RT	1
51+78.79	52+28.78	LT	1
TOTAL			2

**GUARDRAIL REMOVAL**

FROM STATION	TO STATION	LT/RT	FOOT
47+77.24	48+73.74	RT	96.51
51+31.14	52+27.53	LT	96.42
ROUNDED TOTAL			193

**TERMINAL MARKER-DIRECT APPLIED**

STATION	LT/RT	EACH
47+77.47	RT	1
52+28.78	LT	1
TOTAL		2

**PAVEMENT PATCHING SCHEDULE**

STATION	STATION	LT/RT	44201383	X4406440	X4406640	X4421000
			CLASS C PATCHES, TYPE IV, 12 INCH	PARTIAL DEPTH REMOVAL, TYPE III, 4"	PARTIAL DEPTH REMOVAL, TYPE IV, 4"	PARTIAL DEPTH PATCHING
			SQ YD	SQ YD	SQ YD	TON
37+54.20	42+40.32	RT			106.54	22.37
44+41.33	48+01.79	LT		79.13		16.62
55+88.00	56+12.00	CL	26.67			
ROUNDED TOTAL			27	80	107	39

**TEMPORARY CONCRETE BARRIER**

FROM STATION	TO STATION	LT/RT	FOOT
PRE-STAGE 2			
47+42.89	51+55.39	RT	412.50
48+50.59	52+63.09	LT	412.50
ROUNDED TOTAL			825.0

**RELOCATE TEMPORARY CONCRETE BARRIER**

FROM STATION	TO STATION	LT/RT	FOOT
STAGE 1			
<del>46+93.82</del>	<del>47+79.73</del>	<del>RT</del>	<del>87.50</del>
48+13.43	54+62.09	CL	650.00
STAGE 2			
45+63.98	52+37.66	CL	675.00
<del>52+34.82</del>	<del>53+59.31</del>	<del>LT</del>	<del>125.00</del>
ROUNDED TOTAL			1,325.0

**BARRIER WALL REFLECTORS, TYPE C**

FROM STATION	TO STATION	LT/RT	EACH
PRE-STAGE 2			
47+42.89	51+55.39	RT	17
48+50.59	52+63.09	LT	17
TOTAL			34

**IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3**

STATION	LT/RT	EACH
PRE-STAGE 2		
47+29.89	RT	1
52+63.09	LT	1
STAGE 1		
<del>46+93.82</del>	<del>RT</del>	<del>1</del>
TOTAL		2

**IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3**

STATION	LT/RT	EACH
STAGE 1		
48+13.43	RT	1
54+62.09	LT	1
STAGE 2		
45+63.98	RT	1
52+37.66	LT	1
<del>53+59.31</del>	<del>LT</del>	<del>1</del>
TOTAL		4

**GUARDRAIL REFLECTORS, TYPE A**

FROM STATION	TO STATION	LT/RT	EACH
47+77.47	48+66.86	RT	4
51+39.39	52+28.78	LT	4
TOTAL			8

**PAVEMENT MARKING TAPE, TYPE IV 4"**

FROM STATION	TO STATION	LT/RT	FOOT
STAGE 1			
43+72.73	56+18.70	CL	1,252.30
44+22.12	46+89.36	CL	536.91
46+88.93	53+57.43	RT	669.68
46+89.36	53+59.25	RT	1,341.67
53+59.25	55+75.57	CL	436.98
STAGE 2			
44+37.71	46+72.60	CL	286.40
44+41.14	45+81.48	LT	141.16
44+63.14	54+62.77	CL	1,001.96
45+81.39	53+58.63	CL	1,558.42
46+80.03	53+59.07	LT	679.83
53+58.63	55+46.69	LT	378.99
54+62.80	55+55.89	RT	93.17
STAGE 3			
43+96.21	52+40.64	RT	839.98
44+29.47	55+68.93	CL	2,302.10
47+73.39	56+05.27	LT	832.36
ROUNDED TOTAL			12,352

**PAVEMENT MARKING TAPE, TYPE IV - LETTERS AND SYMBOLS**

STATION	LT/RT	SQ FT
STAGE 2		
44+82.03	LT	15.6
45+81.45	LT	15.6
54+62.80	RT	15.6
54+37.80	RT	15.6
ROUNDED TOTAL		63

REV. 10-28-2019