



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 28, 2024

SUBJECT: FAP 600 (IL 159)
Section 19-00025-01-PW (Glen Carbon)
Madison County
Contract No. 97793
Item 133
November 8, 2024 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 14 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

FLARED END SECTION REMOVAL

This item shall be constructed according to Section 605 of the Standard Specifications for Road and Bridge Construction. The end sections shall be removed and properly disposed of by the Contractor. Take care not to damage culvert / storm sewer to remain in place.

This item of work will not be measured and paid for separately but shall be included in the cost of STORM SEWER REMOVAL and no additional compensation will be allowed.

CONCRETE COLLAR

This item shall consist of constructing a concrete collar for the connection of the existing storm sewer pipes to the proposed storm sewer pipes at locations of inlet removal as shown on the plans.

The Contractor shall take special care when making sawcuts into existing storm sewer so as not to damage the existing storm sewer. Prior to installing the concrete collar, the pipe shall be cleared of debris so that the collar will not be resting on or against nor be irregularly supported by such materials.

The concrete shall conform to Section 503 of the Standard Specifications and shall be Class SI. Reinforcing Steel shall conform to Section 508 of the Standard Specifications. All rebar reinforcement required for the construction of the concrete collar shall be considered incidental to the cost of construction and will not be measured for payment.

No additional storm sewer removal, storm sewer placement or aggregate backfill beyond plan quantities will be paid at these locations.

This work shall be paid for at the contract unit price per cubic yard for CONCRETE COLLAR, and no additional compensation will be allowed.

RELOCATE SIGN PANEL ASSEMBLY – TYPE A

This item of work shall consist of furnishing all labor, material and equipment necessary to remove the existing traffic signs (i.e. stop signs, speed signs, etc.) as indicated on the plans, stockpile these signs at the location determined by the Contractor and reinstall the signs in accordance with the plans, the Illinois Manual on Uniform Traffic Control and per the direction of the Engineer. Highway Standards 720001, 720006, and 728001 shall also be referenced.

Any damage to existing signs shall be the responsibility of the Contractor.

This work will be measured (per sign post) and paid for at the contract unit price per EACH for RELOCATE SIGN PANEL ASSEMBLY – TYPE A and no additional compensation will be allowed.

