


CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				90% FED/ 10% STATE	90% FED/ 10% STATE	90% FED/ 10% STATE	100% WEST DUNDEE	100% WEST DUNDEE	
				ROADWAY 0004	TRAFFIC SIGNAL 0021	TRAFFIC SIGNAL INTERCONNECT 0021	LIGHTING 0021	EMERGENCY VEHICLE PREEMPTION (EVP) 0021	
			<i>URBAN</i>						
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	21				21		
84200804	REMOVAL OF POLE FOUNDATION	EACH	27				27		
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6				6		
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1				
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,452		1,452				
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,792		1,449			343	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,528		2,528				
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,807		1,807				
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4,582		4,582				
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	158		158				
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO 14 1C	FOOT	3,885			3,885			
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CABLE, NO. 6 1C	FOOT	589		589				
87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	1		1				
87601100	PEDESTRIAN PUSH BUTTON POST, GALVANIZED STEEL, TYPE I	EACH	1		1				
87700120	STEEL MAST ARM ASSEMBLY AND POLE, 16 FT.	EACH	1		1				
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	1		1				
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2		2				
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1		1				
87702770	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 55 FT. AND 34 FT.	EACH	1		1				
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8		8				
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				

* SPECIALTY ITEM



USER NAME * #USER*	DESIGNED <i>ESI</i>	REVISED -
PLOT SCALE * #SCALE*	DRAWN <i>ESI</i>	REVISED -
PLOT DATE * #DATE*	CHECKED <i>GJS</i>	REVISED -
	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 8 OF 11 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	5-N	KANE	153	11
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60A95	