


CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				90% FED/ 10% STATE	90% FED/ 10% STATE	90% FED/ 10% STATE	100% WEST DUNDEE	100% WEST DUNDEE
				ROADWAY 0004	TRAFFIC SIGNAL 0021	TRAFFIC SIGNAL INTERCONNECT 0021	LIGHTING 0021	EMERGENCY VEHICLE PREEMPTION (EVP) 0021
			<i>URBAN</i>					
• 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	73		73			
• 87900200	DRILL EXISTING HANDHOLE	EACH	5		3	2		
• 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	11		11			
• 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	7		7			
• 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1			
• 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8			
• 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	18		18			
• 88500100	INDUCTIVE LOOP DETECTOR	EACH	14		14			
• 88600100	DETECTOR LOOP, TYPE I	FOOT	1,003		1,003			
• 88700200	LIGHT DETECTOR	EACH	2					2
• 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1					1
• 88800100	PEDESTRIAN PUSH BUTTON	EACH	8		8			
• 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
• 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1			
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	3086			3086		
• 89502380	REMOVE EXISTING HANDHOLE	EACH	13		13			
• 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	11		11			
X5509900	ABANDON AND FILL EXISTING STORM SEWER	FOOT	793	793				
35400475	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 9 3/4"	SQ YD	770	770				
Z0056669	DUCTILE IRON PIPE, 15" STORM SEWER, WATER MAIN QUALITY PIPE 15"	FOOT	4	4				
Z0056668	DUCTILE IRON PIPE, 12" STORM SEWER, WATER MAIN QUALITY PIPE 12"	FOOT	22	22				

• SPECIALTY ITEM



USER NAME • #USER#	DESIGNED <i>ESI</i>	REVISED -
PLOT SCALE • #SCALE#	DRAWN <i>ESI</i>	REVISED -
PLOT DATE • #DATE#	CHECKED <i>GJS</i>	REVISED -
	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 9 OF 11 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	12
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60A95	

Rev.