


CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				90% FED/ 10% STATE	90% FED/ 10% STATE	90% FED/ 10% STATE	100% WEST DUNDEE	100% WEST DUNDEE
				ROADWAY 0004	TRAFFIC SIGNAL 0021	TRAFFIC SIGNAL INTERCONNECT 0021	LIGHTING 0021	EMERGENCY VEHICLE PREEMPTION (EVP) 0021
			<i>URBAN</i>					
X0322024	TRENCH DRAIN	EACH	1	1				
X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	5	5				
X0324085	EMERGENCY VEHICLE PRIORITY SYSTEM LINE SENSOR CABLE, NO. 20 3/C	FOOT	339					339
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	710	710				
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5	5				
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	19	19				
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	16,946	16,946				
Δ X5537800	STORM SEWERS TO BE CLEANED, 12"	FOOT	470	470				
Δ X5537900	STORM SEWERS TO BE CLEANED, 15"	FOOT	74	74				
Δ X5538200	STORM SEWERS TO BE CLEANED, 24"	FOOT	66	66				
X6020094	MANHOLES, TYPE A, 6' - DIAMETER, TYPE I FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	1	1				
X6061100	CONCRETE MEDIAN, TYPE SB (SPECIAL)	SQ FT	855	855				
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	90	90				
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1	0.80	0.20			
X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	6				6	
X8570231	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	1		1			
X8600105	MASTER CONTROLLER (SPECIAL)	EACH	1		1			
X8620200	UNINTERRUPTABLE POWER SUPPLY, SPECIAL	EACH	1		1			
X8710024	FIBER OPTIC CABLE IN CONDUIT, NO 62.5/125, MM12F SM24F	FOOT	3,885			3,885		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	150	150				

Δ SPECIALTY ITEM
Δ 100% STATE (NP)



USER NAME * #USER*	DESIGNED <i>ESI</i>	REVISED -
PLOT SCALE * #SCALE*	DRAWN <i>ESI</i>	REVISED -
PLOT DATE * #DATE*	CHECKED <i>GJS</i>	REVISED -
	DATE <i>07/03/12</i>	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 10 OF 11 SHEETS STA. TO STA.

F.A.U. RTE. 3887	SECTION S-N	COUNTY KANE	TOTAL SHEETS 153	SHEET NO. 13
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60A95	