

TREE REMOVAL & TREE PROTECTION SCHEDULE (1 OF 2)

| LOCATION | OFFSET | 20100110 | 20100210 | 20101000 | 20101100 | 20101200 |
|---------------|----------|----------------------------|-------------------------------|--------------------|--------------------------|----------------------|
| | | TREE REMOVAL 6-15 UNITS | TREE REMOVAL OVER 15 UNITS | TEMPORARY FENCE | TREE TRUNK PROTECTION | TREE ROOT PRUNING |
| | | UNIT | UNIT | FOOT | EACH | EACH |
| IL ROUTE 72 | | | | | | |
| STA 113+78.46 | 38.62 RT | | | 28 | 1 | 1 |
| STA 114+59.99 | 37.28 RT | | 18 | | | |
| STA 114+73.04 | 59.39 LT | | | 37 | 1 | 1 |
| STA 115+45.85 | 61.15 RT | | 24 | | | |
| STA 116+43.45 | 59.63 LT | 14 | | | | |
| STA 11661.33 | 49.01 LT | 8 | | | | |
| STA 116+87.48 | 49.62 LT | 13 | | | | |
| STA 117+06.01 | 48.99 LT | 8 | | | | |
| STA 117+48.35 | 27.19 RT | 4 | | | | |
| STA 117+59.41 | 55.30 LT | 8 | | | | |
| STA 117+89.54 | 49.62 LT | 6 | | | | |
| STA 117+89.54 | 59.33 LT | 6 | | | | |
| STA 117+97.08 | 56.14 LT | 6 | | | | |
| STA 118+11.89 | 56.36 LT | 7 | | | | |
| STA 118+77.20 | 78.55 LT | | | 32 | 1 | 1 |
| STA 119+10.97 | 60.65 LT | | | 56 | 1 | 1 |
| STA 119+32.06 | 54.70 LT | | 20 | | | |
| STA 119+69.41 | 25.32 RT | 7 | | | | |
| STA 120+00.48 | 25.19 RT | 7 | | | | |
| STA 121+82.87 | 38.55 RT | 10 | | | | |
| STA 121+93.31 | 25.77 RT | 8 | | | | |
| STA 122+56.02 | 23.25 RT | | 28 | | | |
| STA 123+25.12 | 32.37 LT | | 30 | | | |
| STA 123+53.74 | 26.87 RT | | 30 | | | |
| STA 123+93.98 | 28.80 RT | | | 50 | 1 | 1 |
| | | | | | | |
| SUB TOTALS | | 112 | 150 | 203 | 5 | 5 |

TREE REMOVAL & TREE PROTECTION SCHEDULE (2 OF 2)

| LOCATION | OFFSET | 20100110 | 20100210 | 20101000 | 20101100 | 20101200 |
|---------------|----------|----------------------------|-------------------------------|--------------------|--------------------------|----------------------|
| | | TREE REMOVAL 6-15 UNITS | TREE REMOVAL OVER 15 UNITS | TEMPORARY FENCE | TREE TRUNK PROTECTION | TREE ROOT PRUNING |
| | | UNIT | UNIT | FOOT | EACH | EACH |
| IL ROUTE 31 | | | | | | |
| STA 204+64.23 | 64.30 RT | | | 18 | 1 | 1 |
| STA 205+31.6 | 44.34 RT | | | 28 | 1 | 1 |
| STA 205+98.11 | 40.09 RT | | | 37 | 1 | 1 |
| STA 207+54.82 | 39.47 RT | | 48 | | | |
| STA 207+86.87 | 40.68 RT | 12 | | | | |
| STA 208+07.27 | 37.65 RT | | 32 | | | |
| STA 209+08.27 | 40.12 RT | 13 | | | | |
| STA 209+13.91 | 39.78 RT | 14 | | | | |
| STA 211+00.96 | 60.56 LT | | | 25 | 1 | 1 |
| STA 213+24.20 | 34.91 RT | 8 | | | | |
| STA 213+38.66 | 34.22 RT | 13 | | | | |
| STA 213+51.36 | 33.59 RT | 8 | | | | |
| STA 213+64.88 | 33.57 RT | 14 | | | | |
| STA 213+78.79 | 33.18 RT | 8 | | | | |
| STA 214+99.88 | 32.56 RT | | | 12 | 1 | 1 |
| STA 215+20.13 | 32.27 RT | | | 12 | 1 | 1 |
| STA 217+30.50 | 32.54 RT | 15 | | | | |
| STA 217+77.58 | 34.77 RT | | | 26 | 1 | 1 |
| STA 218+65.87 | 40.88 RT | | | 24 | 1 | 1 |
| | | | | | | |
| SUB TOTALS | | 105 | 80 | 182 | 8 | 8 |
| TOTALS | | 217 | 230 | 385 | 13 | 13 |



| | | |
|----------------------|----------------------|-----------|
| USER NAME = #USER# | DESIGNED <i>ESI</i> | REVISED - |
| | DRAWN <i>ESI</i> | REVISED - |
| PLOT SCALE = #SCALE# | CHECKED <i>GJS</i> | REVISED - |
| PLOT DATE = #DATE# | DATE <i>07/03/12</i> | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 25 SHEETS STA. TO STA.

| F.A.U. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---------|--------|--------------------|-----------|
| 3887 | S-N | KANE | 153 | 18 |
| | | | CONTRACT NO. 60A95 | |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | |