

PROPOSED EARTHWORK SCHEDULE - STAGE 2 (IL 31) (1 OF 2)

LOCATION			2021200		20400800	
STATION		DISTANCE	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		FURNISHED EXCAVATION	
FROM	TO	FEET	CUT (SQ FT)	CU YD	FILL (SQ FT)	CU YD
203+50	204+00	50	24.3		0	
204+00	204+50	50	8.5	30.4	0	0.00
204+50	205+00	50	17.0	23.6	0	0
205+00	205+12.43	50	22.6	36.7	0	0
205+12.43	205+50	12.43	22.4	41.7	0	0
205+50	206+00	37.57	26.7	11.3	0	0
206+00	206+34.92	50	31.9	40.8	0	0
206+34.92	206+50	34.92	35.8	62.7	0	0
206+50	207+00	15.08	37.5	47.4	0	0
207+00	207+50	50	38.0	21.1	0	0
207+50	208+00	50	46.0	77.8	0	0
208+00	208+50	50	40.0	79.6	0	0
208+50	208+72.78	50	40.1	74.2	0	0
208+72.78	209+00	22.78	41.5	75.6	0	0
209+00	209+50	27.22	40.8	34.7	0	0
209+50	210+00	50	30.5	35.9	0	0
210+00	210+50	50	20.0	46.8	0	0
210+50	211+00	50	15.5	32.9	0	0
211+00	211+32.45	50	14.4	27.7	0	0
211+32.45	211+50	32.45	14.7	26.9	0	0
211+50	213+50	17.55	16.0	18.4	0	0
213+50	214+00	200	20.1	11.7	0	0
214+00	214+50	50	19.2	145.6	0	0
214+50	214+70.16	50	18.6	35.0	0	0
214+70.16	215+00	20.16	19.5	35.3	0	0
215+00	215+50	29.84	20.3	14.9	0	0
215+50	216+00	50	29.7	27.6	0	0
216+00	216+13.25	50	41.5	65.9	0	0
216+13.25	216+50	13.25	45.3	80.4	0	0
216+50	217+00	36.75	53.1	24.1	0	0
217+00	217+50	50	60.3	77.2	0	0
217+50	218+00	50	56.0	107.7	0	0
218+00	218+16.41	50	49.9	98.1	0	0
218+16.41	218+50	16.41	44.8	87.7	0	0
218+50	219+00	33.59	35.3	24.3	0	0
219+00	219+50	50	17.0	32.5	0	0
219+50	219+64.51	50	42.2	54.8	0	0
219+64.51	220+00	14.51	13.0	51.1	0	0
220+00	220+50	35.49	40.9	14.5	0	0
220+50	221+00	50	27.1	44.7	0	0
SUB TOTALS				1879.1		0.00

PROPOSED EARTHWORK SCHEDULE - STAGE 2 (IL 31) (2 OF 2)

LOCATION			2021200		20400800	
STATION		DISTANCE	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		FURNISHED EXCAVATION	
FROM	TO	FEET	CUT (SQ FT)	CU YD	FILL (SQ FT)	CU YD
221+00	221+50	50	23.2	46.6	0	0
221+50	222+00	50	12.0	32.6	0	0
222+00	222+50	50	0.0	11.1	0	0
222+50	222+66.26	50	0.0	0.0	0	0
222+66.26	223+00	16.26	0.0	0.0	0	0
223+00	223+00	33.74	0.0	0.0	0	0
SUB TOTALS				90.3		0.00
TOTALS				1969.4		0.00

PROPOSED EARTHWORK SCHEDULE - STAGE 2 (IL 72)

LOCATION			2021200		20400800	
STATION		DISTANCE	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL		FURNISHED EXCAVATION	
FROM	TO	FEET	CUT (SQ FT)	CU YD	FILL (SQ FT)	CU YD
113+00	113+50	50	0.0			
113+50	114+00	50	0.0	0.0	0	0
114+00	114+17.27	17.27	0.0	0.0	0	0
114+17.27	114+50	32.73	0.0	0.0	0	0
114+50	115+00	50	0.0	0.0	0	0
115+00	117+00	200	0.0	0.0	0	0
117+00	117+31.48	31.48	0.0	0.0	0	0
117+31.48	117+50	18.52	0.0	0.0	0	0
117+50	117+72.49	22.49	0.7	0.2	0	0
117+72.49	118+00	27.51	3.3	1.7	0	0
118+00	118+25.65	25.65	3.4	3.4	0	0
118+25.65	118+50	24.35	3.7	3.4	0	0
118+50	118+88.84	38.84	3.9	3.4	0	0
118+88.84	119+00	11.16	4.0	5.7	0	0
119+00	119+42.32	42.32	4.0	1.7	0	0
119+42.32	119+50	7.68	4.2	6.4	0	0
119+50	120+00	50	4.0	1.2	0	0
120+00	120+50	50	3.2	6.7	0	0
120+50	120+86.94	36.94	3.2	5.9	0	0
120+86.94	121+00	13.06	0.0	2.2	0	0
121+00	121+50	50	0.0	0.0	0	0
121+50	122+00	50	0.0	0.0	0	0
122+00	122+43.51	43.51	0.0	0.0	0	0
122+43.51	122+50	6.49	0.0	0.0	0	0
122+50	123+00	50	0.0	0.0	0	0
123+00	123+50	50	0.0	0.0	0	0
123+50	124+00	50	0.0	0.0	0	0
124+00	124+00	0	3.8	3.5	0	0
TOTALS				45.3		0.0



USER NAME = *USER*	DESIGNED <i>ESI</i>	REVISED -
PLOT SCALE = *SCALE*	DRAWN <i>ESI</i>	REVISED -
PLOT DATE = *DATE*	CHECKED <i>GJS</i>	REVISED -
	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
SCALE: NONE	SHEET NO. 3 OF 25 SHEETS	3887	S-N	KANE	153	20
		STA. TO STA.		CONTRACT NO. 60A95		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT						