

GEO FABRIC & PGES SCHEDULE

LOCATION	21001000	30300001		
	GEO FABRIC FOR GROUND STABILIZATION SQ YD	AGGREGATE SUBGRADE IMPROVEMENT		
		AREA SQ YD	DEPTH FOOT	VOLUME CU YDS
IL ROUTE 72				
STA 113+47 TO STA 117+80	798.0	7182.0	1.167	310.3
STA 117+80 TO STA 121+20	857.7	7719.6	1.000	285.9
IL ROUTE 31				
STA 204+60 TO STA 208+75	1306.6	11759.8	1.000	435.5
STA 208+75 TO STA 211+50	771.4	6942.9	1.000	257.1
STA 211+50 TO STA 214+75	611.6	5504.7	1.167	237.9
STA 214+75 TO STA 220+00	1544.5	13900.5	1.000	514.8
TOTALS	5889.9			2041.6

LANDSCAPE SCHEDULE

LOCATION	20101400	20101500	201001600	21101625	25200110	25200200	66400105
	NITROGEN FERTILIZER NUTRIENT POUND	PHOSPHORUS FERTILIZER NUTRIENT POUND	POTASSIUM FERTILIZER NUTRIENT POUND	TOPSOIL FURNISH AND PLACE 6" SQ YD	SODDING SALT TOLERANT SQ YD	SUPPLEMENTAL WATERING UNIT	CHAIN LINK FENCE 4' FOOT
IL ROUTE 72							
STA 112+69.07 TO STA 118+50.00	9.8	9.8	9.8	787.0	787.0	39.3	0.0
STA 118+50.00 TO STA 124+33.29	8.5	8.5	8.5	688.2	688.2	34.4	0.0
IL ROUTE 31							
STA 203+19.37 TO STA 209+00.00	6.8	6.8	6.8	546.7	546.7	27.3	0.0
STA 209+00.00 TO STA 211+60.00	3.1	3.1	3.1	247.0	247.0	12.3	90.2
STA 213+50.00 TO STA 215+00.00	0.6	0.6	0.6	52.2	52.2	2.6	0.0
STA 215+00.00 TO STA 219+00.00	2.1	2.1	2.1	170.2	170.2	8.5	0.0
STA 219+00.00 TO STA 223+07.84	2.3	2.3	2.3	184.4	184.4	9.2	0.0
TOTALS	33.2	33.2	33.2	2675.6	2675.6	133.8	90.2

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.



USER NAME = *USER*	DESIGNED <i>ESI</i>	REVISED - <i>08/01/12</i>
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = *SCALE*	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = *DATE*	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 25 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	21
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				