

ROADWAY REMOVAL SCHEDULE

	44000100	44000500	44000600	44003100	44300200	X4401198	X6640300
LOCATION	PAVEMENT REMOVAL	COMB C & G REMOVAL	SIDEWALK REMOVAL	MEDIAN REMOVAL	STRIP REFLECTIVE CRACK CONTROL	HMA SURF. VAR DEPTH REMOVAL	CHAIN LINK FENCE REMOVAL
	SQ YD	FOOT	SQ YD	SQ YD	FOOT	SQ YD	FOOT
IL ROUTE 72							
STA 112+69.07 TO STA 118+50.00	257.5	1420.3	4447.8	431.7	2072.4	4448.0	0.0
STA 118+50.00 TO STA 124+33.29	528.7	1227.8	5964.6	0.0	2052.6	3023.7	0.0
IL ROUTE 31							
STA 203+19.37 TO STA 209+00.00	470.3	1206.3	2316.9	9244.2	2357.0	2970.9	0.0
STA 209+00.00 TO STA 211+60.00	134.8	521.8	1289.8	1802.4	1041.2	1857.2	90.0
STA 213+50.00 TO STA 215+00.00	103.1	299.9	1012.2	621.7	600.0	914.0	0.0
STA 215+00.00 TO STA 219+00.00	305.1	799.7	2849.5	5225.2	1576.9	2145.6	0.0
STA 219+00.00 TO STA 223+07.84	174.4	446.5	1941.0	2680.2	603.2	1586.6	0.0
TOTALS	1973.9	5922.4	19821.7	20005.5	10303.3	16946.1	90.0

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.

DRIVEWAY REMOVAL SCHEDULE (1 OF 2)

		44000200	44000300	44000500
LOCATION	LT/RT	DRV PVMNT REMOVAL	CURB REMOVAL	COMB C & G REMOVAL
		SQ FT	FOOT	FOOT
IL ROUTE 72				
STA. 113+20.51	RT	118.2	46.1	0.0
STA. 114+16.95	RT	58.3	27.7	0.0
STA. 115+00.00	RT	67.1	35.5	0.0
STA. 117+31.10	LT	131.4	123.0	0.0
STA. 117+72.05	LT	80.1	0.0	0.0
STA. 118+11.88	RT	60.3	0.0	0.0
STA. 118+24.42	LT	55.0	0.0	0.0
STA. 118+88.87	RT	28.9	0.0	0.0
STA. 118+94.29	LT	75.5	68.7	0.0
STA. 119+42.58	RT	27.5	0.0	0.0
STA. 122+43.68	RT	19.3	0.0	0.0
STA. 122+45.76	LT	19.5	0.0	0.0
STA. 122+99.3	RT	22.8	0.0	0.0
SUB TOTALS		763.9	301.0	0.0

DRIVEWAY REMOVAL SCHEDULE (2 OF 2)

		44000200	44000300	44000500
LOCATION	LT/RT	DRV PVMNT REMOVAL	CURB REMOVAL	COMB C & G REMOVAL
		SQ FT	FOOT	FOOT
IL ROUTE 31				
STA. 203+43.36	LT	20.5	17.6	0.0
STA. 204+97.65	RT	9.1	0.0	0.0
STA. 203+36.68	RT	50.0	0.0	0.0
STA. 207+03.89	RT	50.9	0.0	0.0
STA. 208+13.66	LT	92.5	60.5	0.0
STA. 210+58.89	LT	42.1	0.0	25.2
STA. 211+40.80	LT	62.6	0.0	40.6
STA. 211+43.36	RT	102.1	0.0	119.5
STA. 214+04.36	RT	27.4	22.1	0.0
STA. 214+69.99	RT	47.2	6.6	0.0
STA. 215+48.38	RT	46.5	6.2	0.0
STA. 217+36.50	LT	64.5	0.0	27.9
STA. 218+17.79	RT	82.5	38.0	0.0
SUB TOTALS		697.9	151.0	213.2
TOTALS		1461.8	452.0	213.2



USER NAME = #USER#	DESIGNED <i>ESI</i>	REVISED -
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = #SCALE#	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = #DATE#	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE: NONE	SHEET NO. 5 OF 25 SHEETS
STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	22
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				