

**PROPOSED PAVING SCHEDULE (1 OF 2)**

LOCATION	31101200	35101600	35300300	35300415	35400300	*1009256	40600200	40600300	40603240	40603595
	SUB GRAN MATR TYPE B, 4"	AGGREGATE BASE COURSE TYPE B, 4"	PCC BASE CRSE 8"	PCC BASE CRSE 9 3/4"	PCC BASE CRSE WIDENING 8"	PCC BASE CRSE WIDEN 9 3/4"	BIT MATR (PRIME COAT)	AGGREGATE (PRIME COAT)	POLY HMA BNDER CRSE IL-19.0, N90	POLY HMA SURF CRSE MIX "F", N90
	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	FOOT	FOOT
IL ROUTE 72										
STA 112+69.07 TO STA 118+50.00	1450.1	14.3	647.9	84.6	52.3	103.0	4.2	21.3	659.3	513.1
STA 118+50.00 TO STA 124+33.29	1165.3	57.2	381.1	0.0	173.4	0.0	3.3	14.3	435.3	338.6
IL ROUTE 31										
STA 203+19.37 TO STA 209+00.00	1883.0	28.1	0.0	936.9	0.0	163.9	4.4	16.3	512.6	398.7
STA 209+00.00 TO STA 211+60.00	698.9	0.0	0.0	135.6	0.0	235.1	1.8	8.9	280.5	218.1
STA 213+50.00 TO STA 215+00.00	369.8	0.0	0.0	84.0	0.0	101.8	0.9	4.4	138.6	107.8
STA 215+00.00 TO STA 219+00.00	1235.3	27.1	0.0	595.5	0.0	156.1	2.5	11.6	364.4	283.4
STA 219+00.00 TO STA 223+07.84	556.2	0.0	0.0	299.9	0.0	10.0	1.6	7.6	238.8	185.7
TOTALS	7358.6	126.7	1029.0	2136.4	225.8	769.8	18.7	84.4	2629.5	2045.4

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50)  
QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.

**PROPOSED PAVING SCHEDULE (2 OF 2)**

LOCATION	42400200	42400800	60603800	60605000	60608300	60619200	60619600	60626300	60618300	X6061100
	PCC SIDEWALK 5"	DETECTABLE WARNINGS	COMC CONC C&G TY B-6.12	COMC CONC C&G TY B-6.24	COMB CONC C&G TY M-2.12	CONC MED TY SB-6.06	CONC MED TY SB-6.12	STABILIZED MEDIAN SURF 12"	CONC MED SURFACE 4"	CONC MED TY SB (SPECIAL)
	SQ FT	SQ FT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ YD	SQ YD	SQ FT
IL ROUTE 72										
STA 112+69.07 TO STA 118+50.00	6277.8	105.8	0.0	1085.3	0.0	1518.2	0.0	0.0	14.3	0.0
STA 118+50.00 TO STA 124+33.29	6642.3	56.6	670.2	1166.6	0.0	480.6	75.5	191.3	57.2	0.0
IL ROUTE 31										
STA 203+19.37 TO STA 209+00.00	3014.8	55.2	0.0	1190.9	910.9	199.8	50.5	537.1	28.1	254.2
STA 209+00.00 TO STA 211+60.00	2240.6	0.0	0.0	520.5	0.0	1040.2	0.0	0.0	0.0	0.0
STA 213+50.00 TO STA 215+00.00	1816.0	0.0	0.0	299.9	0.0	600.0	0.0	0.0	0.0	0.0
STA 215+00.00 TO STA 219+00.00	5000.8	53.9	299.0	796.8	0.0	400.0	0.0	81.1	27.1	600.5
STA 219+00.00 TO STA 223+07.84	4320.5	29.7	112.9	415.5	0.0	800.6	0.0	51.5	0.0	0.0
TOTALS	29312.8	301.2	1082.1	5475.5	910.9	5039.4	126.0	861.0	126.7	854.7

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50)  
QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.



USER NAME = *USER*	DESIGNED <i>ESI</i>	REVISED - <i>08/01/12</i>
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = *SCALE*	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = *DATE*	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NONE      SHEET NO. 8 OF 25 SHEETS      STA.      TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	25
CONTRACT NO. 60A95			FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT	