

DRAINAGE AND UTILITY STRUCTURAL ADJUSTMENT SCHEDULE

STRUCTURE NUMBER	LOCATION	OFFSET	60250500	60251500	60251740	60255500	602658200	60259340	60260100	60265700	60404800	60404950	60406100	XX003424
			CB TO BE ADJ W/NEW TY I F&CL	CB TO BE ADJ W/NEW TY 11 F&G	CB TO BE ADJ W/NEW TY 24 F&G	MANHOLE TO BE ADJUSTED	MH TO BE ADJ W/NEW TY 1 F&CL	MH TO BE RECON W/NEW TY 24 F&G	INLETS TO BE ADJUST	VALVE VAULTS TO BE ADJ	FRAMES AND GRATES, TY 11	FRAMES AND GRATES, TY 24	FRAMES AND LID, TY 1, CL	PROP SS CONNECT TO EXIST MANHOLE
			EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
	IL ROUTE 72													
ST-3	STA. 114+22.51	42.6' LT						1						
ST-28	STA. 114+56.81	23.1' RT					1							1
SAN	STA. 116+59.98	30.7' RT				1							1	
SAN	STA. 116+83.35	2.4' RT				1							1	
VV	STA. 116+95.89	17.81' LT								1				
ST-7	STA. 117+01.61	37.8' LT				1							1	1
VV	STA. 117+11.36	19.43' LT								1				
SAN	STA. 117+17.56	1.2' RT				1							1	
SAN	STA. 117+43.08	63.6' LT				1							1	
ST-12	STA. 120+52.43	38.6' LT						1						
ST-22	STA. 120+67.88	21.0' LT				1							1	
SAN	STA. 120+84.52	2.85' LT				1							1	
	IL ROUTE 31													
EXIST	STA. 203+19.74	41.8' LT										1		
ST-30	STA. 203+22.46	22.5' RT			1									1
VV	STA. 204+80.36	26.53' RT								1				
VV	STA. 205+22.19	30.63' RT								1				
ST-35b	STA. 205+44.63	51.4' LT												1
VV	STA. 205+44.70	25.4' RT								1				
ST-39	STA. 205+50.60	22.0' RT			1									
VV	STA. 206+66.68	22.49' RT								1				
ST-42	STA. 207+21.30	21.3' RT	1											
VV	STA. 208+80.94	38.23' RT								1				
ST-48c	STA. 211+22.22	32.3' RT	1											
ST-48d	STA. 211+28.83	37.1' RT							1					
ST-48a	STA. 211+67.62	54.3' LT				1							1	
ST-48	STA. 213+15.40	57.2' LT						1						
ST-59	STA. 216+05.20	47.8' RT												1
VV	STA. 216+30.22	26.5' RT								1				
ST-63	STA. 217+51.98	47.7' LT			1									
EXIST	STA. 219+45.17	52.32' RT							1		1			
EXIST	STA. 219+71.74	60.45' RT							1		1			
ST-69	STA. 221+46.55	40.1' RT			1									
ST-70	STA. 221+47.57	12.0' LT		1										
		TOTALS	2	1	4	8	1	3	3	8	2	1	8	5



USER NAME = *USER*	DESIGNED <i>ESI</i>	REVISED - 08/01/12
PLOT SCALE = *SCALE*	DRAWN <i>ESI</i>	REVISED - 08/29/12
PLOT DATE = *DATE*	CHECKED <i>GJS</i>	REVISED -
	DATE 07/03/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: NONE	SHEET NO. 11 OF 25 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	28
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				