

**PROPOSED STORM SEWER SCHEDULE**

LOCATION	20800150	STORM SEWERS, CLASS A, TYPE 2					SS A, TY2 WMQP		61139900	61140000	60107700	X5537800	X5537900	X5538200
	TRENCH BACKFILL	550A0340	550A0360	550A0410	550A0450	550A0470	Z0056668	Z0056669	SS SPECIAL 6"	SS SPECIAL 8"	PIPE UD 6"	SS TO BE CLEANED 12"	SS TO BE CLEANED 15"	SS TO BE CLEANED 24"
	CU YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL ROUTE 72														
STA 112+69.07 TO STA 118+50.00	32.1	398	0	0	0	0	0	0	0	0	0	0	74	66
STA 118+50.00 TO STA 124+33.29	51.1	276	0	7	0	0	8	0	0	0	0	51	0	0
IL ROUTE 31														
STA 203+19.37 TO STA 209+00.00	52.7	248	0	0	0	5	0	4	19	0	140	204	0	0
STA 209+00.00 TO STA 211+60.00	35.7	58	0	0	0	0	4	0	0	0	50	163	0	0
STA 213+50.00 TO STA 215+00.00	4.2	0	0	0	194	0	6	0	0	0	0	0	0	0
STA 215+00.00 TO STA 219+00.00	47.8	0	93	0	72	0	4	0	0	14	0	0	0	0
STA 219+00.00 TO STA 223+07.84	18.2	69	0	0	0	0	0	0	0	0	0	52	0	0
TOTALS	241.9	1049	93	7	266	5	22	4	19	14	190	470	74	66

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.

**EROSION CONTROL SCHEDULE**

LOCATION	STAGE 1			STAGE 2			STAGE 3		
	28000250	28000400	28000510	28000250	28000400	28000510	28000250	28000400	28000510
	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS
	POUND	FOOT	EACH	POUND	FOOT	EACH	POUND	FOOT	EACH
IL ROUTE 72									
STA 112+69.07 TO STA 118+50.00	16.1	769.9	6	48.9	0.0	6	0.0	0.0	3
STA 118+50.00 TO STA 124+33.29	26.0	997.1	6	30.8	0.0	6	0.0	0.0	0
IL ROUTE 31									
STA 203+19.37 TO STA 209+00.00	24.1	988.8	4	21.1	0.0	6	0.0	0.0	3
STA 209+00.00 TO STA 211+60.00	15.0	428.9	3	5.4	41.0	1	0.0	0.0	2
STA 213+50.00 TO STA 215+00.00	3.6	232.6	3	0.7	0.0	1	0.0	0.0	0
STA 215+00.00 TO STA 219+00.00	10.2	624.8	3	3.8	0.0	2	0.0	0.0	1
STA 219+00.00 TO STA 223+07.84	11.4	354.9	3	3.9	0.0	2	0.0	0.0	3
TOTALS	106.4	4396.9	28	114.6	41.0	24	0.0	0.0	12

NOTES:

- SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50) QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.
- TEMPORARY EROSION CONTROL SEEDING - UNIFORM COVERAGE RATE OF 100 LBS/ACRE APPLIED 4 TIMES THROUGHOUT DURATION OF PROJECT.



USER NAME = *USER*	DESIGNED <i>ESI</i>	REVISED - <i>08/01/12</i>
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = *SCALE*	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = *DATE*	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES</b>	
SCALE: NONE	SHEET NO. 12 OF 25 SHEETS
STA.	TO STA.

F.A.U. RTÉ.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	29
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1   ILLINOIS FED. AID PROJECT				