

PRE-STAGE & STAGE 1 PAVEMENT MARKING SCHEDULE

LOCATION	PRE-STAGE 1 REMOVALS					STAGE 1 PAVEMENT MARKINGS					
	78300100					78300200	70300510	70300520		70300540	70300570
	PVMNT MRKNG REMOVAL					RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PAVEMENT MARKING TAPE, TYPE III LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE TYPE III			
	4"	6"	12"	24"	LETTERS & SYMBOLS			4"		6"	24"
SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	EACH	SQ FT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	
IL ROUTE 72											
STA 112+69.07 TO STA 124+33.29	125.0	48.5	133.0	72.0	0.0	19.0	0.0	1673.0	0.0	137.2	0.0
IL ROUTE 31											
STA 203+19.37 TO STA 211+00.00	87.0	48.5	0.0	0.0	0.0	10.0	0.0	1374.0	0.0	0.0	0.0
STA 215+00.00 TO STA 223+07.84	45.7	0.0	0.0	0.0	0.0	6.0	0.0	907.0	0.0	0.0	0.0
SUB TOTALS	257.7	97.0	133.0	72.0	0.0			3954.0	0.0	137.2	0.0
TOTALS	559.7					35.0	0.0	3954.0		137.2	0.0

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50)
QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.

PRE-STAGE & STAGE 2 PAVEMENT MARKING SCHEDULE

LOCATION	PRE-STAGE 2 REMOVALS					STAGE 2 PAVEMENT MARKINGS					
	78300100					78300200	70300510	70300520		70300540	70300570
	PVMNT MRKNG REMOVAL					RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	PAVEMENT MARKING TAPE, TYPE III LETTERS AND SYMBOLS	PAVEMENT MARKING TAPE TYPE III			
	4"	6"	12"	24"	LETTERS & SYMBOLS			4"		6"	24"
SQ FT	SQ FT	SQ FT	SQ FT	SQ FT	EACH	SQ FT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE FOOT	
IL ROUTE 72											
STA 112+69.07 TO STA 124+33.29	129.3	0.0	144.4	64.0	0.0	17.0	0.0	1885.0	0.0	149.4	0.0
IL ROUTE 31											
STA 203+19.37 TO STA 211+00.00											
STA 215+00.00 TO STA 223+07.84	87.0	0.0	0.0	0.0	0.0	10.0	0.0	832.0	0.0	0.0	0.0
	71.7	0.0	0.0	0.0	0.0	8.0	0.0	1131.0	0.0	0.0	0.0
SUB TOTALS	288.0	0.0	144.0	64.0	0.0			3848.0	0.0	149.4	0.0
TOTALS	496.0					35.0	0.0	3848.0		149.4	0.0

NOTE: SCHEDULE LISTED ARE SEPARATED BY SHEETS. IL 31 (STATION 211+60 TO STATION 213+50)
QUANTITIES HAVE BEEN INCLUDED BETWEEN STATION 112+69.07 TO STATION 118+50.



USER NAME = #USER#	DESIGNED <i>ESI</i>	REVISED -
DRAWN <i>ESI</i>	REVISOR -	
CHECKED <i>GJS</i>	REVISOR -	
DATE <i>07/03/12</i>	REVISOR -	

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: NONE	SHEET NO. 17 OF 25 SHEETS	STA.	TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	34
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

CONTRACT NO. 60A95