

EXISTING SIGNING REMOVALS & RELOCATIONS (2 OF 3)

PANEL DESCRIPTION	EXISTING SIZES		EXISTING SIGN LOCATIONS			72400100	72400200	72400310	72400720
	WIDTH	HEIGHT	STATION	OFFSET	LT/RT	REMOVE SIGN PANEL ASSEMBLY - TY A	REMOVE SIGN PANEL ASSEMBLY - TY B	REMOVE SIGN PANEL TYPE 1	RELOCATE SIGN PANEL TYPE 2
	INCHES	INCHES				EACH	EACH	SQ FT	SQ FT
IL ROUTE 72									
EAST	24	12	116+79.83	28.60'	RT	-	-	2.0	-
STATE ROUTE	24	24	118+09.13	45.14'	LT	1	-	-	-
DIRECTIONAL ARROW	21	15	118+09.13	45.14'	LT	-	-	-	-
SPEED LIMIT	30	36	118+66.70	24.38'	RT	1	-	-	-
NO PARKING	12	18	118+66.70	24.38'	RT	-	-	-	-
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
SCHOOL CROSSING	36	36	119+98.92	39.30'	LT	-	1	-	-
NO PARKING	12	18	119+98.92	39.30'	LT	-	-	-	-
HISTORICAL MUSEUM (SALVAGE)	24	24	120+43.11	24.16'	RT	1	-	-	-
STOP	30	30	120+68.67	51.46'	LT	1	-	-	-
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
ONE-WAY	-	-	-	-	-	-	-	-	-
ONE-WAY	-	-	-	-	-	-	-	-	-
"Main St." (SALVAGE)	8	36	121+05.56	50.12'	LT	1	-	-	-
"Seventh St." (SALVAGE)	8	36	121+05.56	50.12'	LT	-	-	-	-
STOP	30	30	121+06.97	37.48'	RT	1	-	-	-
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
HISTORICAL MUSEUM (SALVAGE)	24	24	121+27.76	38.20'	LT	1	-	-	-
JUNCTION	20	12	122+72.32	32.28'	LT	1	-	-	-
STATE ROUTE	24	24	122+72.32	32.28'	LT	-	-	-	-
SPEED LIMIT	30	36	123+92.37	27.61'	LT	1	-	-	-
NO PARKING	12	18	123+92.37	27.61'	LT	-	-	-	-
IL ROUTE 31									
STOP	30	30	205+31.91	38.10'	RT	1	-	-	-
"Eighth St." (SALVAGE)	8	36	205+44.89	34.53'	RT	1	-	-	-
"Liberty St." (SALVAGE)	8	36	205+44.89	34.53'	RT	-	-	-	-
SCHOOL CROSSING	36	36	205+58.07	30.88'	RT	1	-	-	-
JUNCTION	30	21	206+64.21	31.48'	LT	-	1	-	-
STATE ROUTE	36	36	206+64.21	31.48'	LT	-	-	-	-
DUAL LEFT TURN LANE ONLY	-	-	-	-	-	-	-	-	-
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
STOP	30	30	208+90.40	48.27'	RT	1	-	-	-
RIGHT TURN ONLY	-	-	-	-	-	-	-	-	-
SUB TOTALS						13	2	2.0	0.0



USER NAME = #USER#	DESIGNED <i>ESI</i>	REVISED -
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = #SCALE#	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = #DATE#	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 21 OF 25 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	38
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				