

NEW SIGNING (1 OF 3)

PANEL DESCRIPTION	PROPOSED SIZES		PROPOSED SIGN LOCATIONS			72000100	72000200	72300100	72900100	72900200	
	WIDTH INCHES	HEIGHT INCHES	STATION	OFFSET	LT/RT	SIGN PANEL TYPE 1	SIGN PANEL TYPE 2	INSTALL EXISTING SIGN PANEL	METAL POST TYPE A	METAL POST TYPE B	
						SQ FT	SQ FT	SQ FT	FOOT	FOOT	
IL ROUTE 72											
RIGHT TURN ONLY	30	36	112+49.24	57.68'	LT	7.5	-	-	-	-	
RIGHT TURN ONLY	30	36	113+21.05	38.75'	RT	7.5	-	-	10.5	-	
STOP	30	30	113+44.43	40.07'	RT	6.25	-	-	10.5	-	
STATE ROUTE	24	24	113+67.41	28.55'	RT	4.0	-	-	10.5	-	
DIRECTIONAL ARROW	21	15	113+67.41	28.55'	RT	2.2	-	-	-	-	
LAND OF LINCOLN (SALVAGE)	24	30	114+16.21	56.33'	RT	-	-	5.0	-	11	
ADOPT A HIGHWAY (SALVAGE)	24	18	114+16.21	56.33'	RT	-	-	3.0	-	-	
KEEP ILLINOIS CLEAN (SALVAGE)	36	36	114+16.21	56.33'	RT	-	-	9.0	-	-	
WEST	24	12	115+01.12	60.80'	LT	2.0	-	-	10.5	-	
STATE ROUTE	24	24	115+01.12	60.80'	LT	4.0	-	-	-	-	
IL RT 31	60	30	MOUNTED ON MAST ARM (NWC)			-	12.5	-	-	-	
DIRECTIONAL ARROW	21	15	MOUNTED ON TRAFFIC SIGNAL POST (NWC)			2.2	-	-	-	-	
STATE ROUTE	24	24				4.0	-	-	-	-	-
SCHOOL CROSSING	36	36				9.0	-	-	-	-	-
STOP	30	30				6.25	-	-	-	-	-
LEFT ON GREEN ARROW ONLY	24	30				5.0	-	-	-	-	-
SCHOOL CROSSING	36	36				9.0	-	-	-	-	-
STOP	30	30	MOUNTED ON TRAFFIC SIGNAL POST (SWC)			6.25	-	-	-	-	
IL RT 72	60	30	MOUNTED ON MAST ARM (SWC)			-	12.5	-	-	-	
LEFT ON GREEN ARROW ONLY	24	30	TRAFFIC SIGNAL POST (SWC)			5.0	-	-	-	-	
PHOTO ENFORCED (SALVAGE)	24	24	116+41.94	79.35'	LT	-	-	4.0	10.5	-	
SCHOOL CROSSING	36	36	MOUNTED ON TRAFFIC SIGNAL POST (SEC)			9.0	-	-	-	-	
STOP	30	30				6.25	-	-	-	-	-
IL RT 31	60	30	MOUNTED ON MAST ARM (SEC)			-	12.5	-	-	-	
LEFT ON GREEN ARROW ONLY	24	30	TRAFFIC SIGNAL POST (SEC)			5.0	-	-	-	-	
"Eighth St." (SALVAGE)	36	8	116+47.62	60.85'	LT	-	-	2.0	10.5	-	
"Main St." (SALVAGE)	36	8	116+47.62	60.85'	LT	-	-	2.0	-	-	
IL RT 72	60	30	MOUNTED ON MAST ARM (NEC)			-	12.5	-	-	-	
LEFT ON GREEN ARROW ONLY	24	30	MOUNTED ON TRAFFIC SIGNAL POST (NEC)			5.0	-	-	-	-	
SCHOOL CROSSING	36	36				9.0	-	-	-	-	-
STOP	30	30				6.25	-	-	-	-	-
STATE ROUTE	24	24	116+53.13	71.17'	RT	4.0	-	-	10.5	-	
DIRECTIONAL ARROW	21	15	116+53.13	71.17'	RT	2.2	-	-	-	-	
STATE ROUTE	24	24	117+67.69	29.17'	RT	4.0	-	-	10.5	-	
SUB TOTALS						130.8	50.0	25.0	84.0	11	



USER NAME = #USER#	DESIGNED <i>ESI</i>	REVISED -
	DRAWN <i>ESI</i>	REVISED -
PLOT SCALE = #SCALE#	CHECKED <i>GJS</i>	REVISED -
PLOT DATE = #DATE#	DATE <i>07/03/12</i>	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 23 OF 25 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3887	S-N	KANE	153	40
CONTRACT NO. 60A95				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				