SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK		
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	19	19					
	20100500	TREE REMOVAL, ACRES	ACRE	0.03	0.03					
	20200100	EARTH EXCAVATION	CU YD	463	463					
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	550	550					
	20800150	TRENCH BACKFILL	CU YD	82	82					
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	656	656					
*	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2607	2607					
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	33	33					
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	33	33					
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	33	33					
*	25100630	EROSION CONTROL BLANKET	SQ YD	2607	2607					
*	25200110	SODDING, SALT TOLERANT	SQ YD	2607	2607					
*	25200200	SUPPLEMENTAL WATERING	UNIT	131	131					
	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	54	54					
	28000400	PERIMETER EROSION BARRIER	FOOT	646	646					
	28000510	INLET FILTERS	EACH	11	11					
	35600704	HOT-MIX ASPHALT BASE COURSE WIDENING, 7"	SQ YD	347	347					
	30300112	AGGREGATE SUBGRADE IMPROVEMENT, 12"	SQ YD	656	656					
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2					
	40600300	AGGREGATE (PRIME COAT)	TON	9	9					
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	7	7					
	40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	98	98					
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	492	492					
	42001300	PROTECTIVE COAT	SQ YD	711	711					
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4005				4005		
	42400800	DETECTABLE WARNINGS	SQ FT	189				189		
	44000100	PAVEMENT REMOVAL	SQ YD	166	166					
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4111	4111					
	44000300	CURB REMOVAL	FOOT	6	6					
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	740	740					
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	400	400					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	6	6					
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1	1					
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1					
54214515	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 30"	EACH	1	1					
54248150	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 30"	EACH	1	1					
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	48	48					
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	50	50					
550A4000	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	110	110					
550A4100	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	96	96					
550A4300	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 30"	FOOT	300	300					
55100500	STORM SEWER REMOVAL 12"	FOOT	20	20					
55100700	STORM SEWER REMOVAL 15"	FOOT	5	5					
55100900	STORM SEWER REMOVAL 18"	FOOT	115	115					
55101200	STORM SEWER REMOVAL 24"	FOOT	100	100					
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	4	4					
60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3					
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1					
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1					
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1					
60500040	REMOVING MANHOLES	EACH	1	1					
60500050	REMOVING CATCH BASINS	EACH	1	1					
60500060	REMOVING INLETS	EACH	7	7					
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3					
60600605	CONCRETE CURB, TYPE B	FOOT	6	6					
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	22	22					

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\paryroot\d0713204\P142209 Design.dgn	USER NAME = paryroot	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/7/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 58 AT SHALES PKWY.

SCALE: NONE | SHEET NO. 1 OF 3 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	581-N-1	COOK	50	3
		CONTRACT NO. 60L43		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT