SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK		
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	18	18					
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	765	765					
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
	67100100	MOBILIZATION	L SUM	1	1					
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1					
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6					
	70300100	SHORT TERM PAVEMENT MARKING	FOOT	1717	1717					
	70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	146	146					
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2093	2093					
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1111	1111					
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	79	79					
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	96	96					
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	102	102					
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1941	1941					
*	72000100	SIGN PANEL - TYPE 1	SQ FT	18		18				
*	72000200	SIGN PANEL - TYPE 2	SQ FT	50		50				
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146					
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2093	2093					
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1111	1111					
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	79	79					
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	96	96					
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	102	102					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	52	52					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	42	42					
*	80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1		1				

SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	TOTAL QUANTITIES (URBAN)	0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK		
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	851		851				
*	81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	58		58				
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	103		103				
*	81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	414		414				
*	81400100	HANDHOLE	EACH	3		3				
*	81400200	HEAVY-DUTY HANDHOLE	EACH	4		4				
*	81400300	DOUBLE HANDHOLE	EACH	2		2				
*	84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	1	1					
*	84200804	REMOVAL OF POLE FOUNDATION	EACH	1		1				
*	85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
*	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1245		1245				
*	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1810		1810				
*	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	781		781				
*	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1463		1463				
*	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1860		1860				
*	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	132		132				
*	87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	829		829				
*	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4				
*	87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1		1				
*	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1				
*	87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1		1				
*	87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1		1				
*	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16				
*	87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4				
*	87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10		10				
*	87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	37		37				

* SPECIALTY ITEMS

FILE NAME = c:\pw_work\pwidot\paynoah\d0273204\I142209 Design.dgn	USER NAME = paynoah	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 2/7/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL. RTE. 58 AT SHALES PKWY.

SCALE: NONE | SHEET NO. 2 OF 3 SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1320	581-N-1	COOK	50	4
		CONTRACT NO. 60L43		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT