

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK			CODE NO	ITEM		UNIT	0004 90% FED 10% STATE ROADWAY	0021 90% FED 5% STATE 5% ELGIN T. SIGNALS	0021 100% ELGIN EVP	0021 80% STATE 20% ELGIN SIDEWALK	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1463	1463					* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	37	37					
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1860	1860					* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	4	4					
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	132	132					* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4	4					
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	829	829					* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4	4					
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4	4					* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8	8					
* 87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1	1					* 88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	8	8					
* 87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1	1					* 88500100	INDUCTIVE LOOP DETECTOR	EACH	9	9					
* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1					* 88600100	DETECTOR LOOP, TYPE I	FOOT	885	885					
* 87700290	STEEL MAST ARM ASSEMBLY AND POLE, 50 FT.	EACH	1	1					* 88700200	LIGHT DETECTOR	EACH	2			2			
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16	16					* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1			1			
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4					* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8					
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10	10														
* SPECIALTY ITEMS																		