

EARTHWORK SCHEDULE

| 1 LOCATION | 2 EARTH EXCAVATION CUBIC YARD | 3 EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CUBIC YARD | 4 EMBANKMENT CUBIC YARD | 5 EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CUBIC YARD |
|---------------|--|--|-------------------------------|--|
| IL. RTE. 58 | 247 | 210 | 236 | -26 |
| SHALES PKWY. | 216 | 183 | 13 | 170 |
| TOTAL | 463 | 393 | 249 | 144 |

COLUMNS 1, 2, & 4 LOCATION AND QUANTITIES FROM CROSS SECTIONS:
CUT = EARTH EXCAVATION, FILL = EMBANKMENT

COLUMN 3 QUANTITY OF EARTH EXCAVATION (CUT) ADJUSTED FOR SHRINKAGE FACTOR OF 15%.

COLUMN 5 EARTHWORK REQUIRED:
(-) = QUANTITY OF FILL OR EMBANKMENT NEEDED (FURNISHED OR BORROW EXCAVATION)
(+) = QUANTITY TO BE WASTED.