



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 31, 2012

SUBJECT: FAP Route 347(IL 38)  
Project ACH-SIP-0347(029)  
Section CY-TS-1(12)  
DuPage County  
Contract No. 60T79  
Item No. 66, November 9, 2012 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page iii of the Table of Contents to the Special Provisions.
3. Revised pages 128-131 of the Special Provisions.
4. Revised sheet 7 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John Baranzelli,  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read "Ted B. Walschleger P.E." with a stylized flourish.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Mike Renner; Estimates

dr

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 60T79

State Job # - C-91-441-12

County Name - DUPAGE - -

Code - 43 - -

District - 1 - -

Section Number - CY-TS-1 (12)

Project Number  
 ACHSIP-0347/029/

Route  
 FAP 347

\*REVISED: OCTOBER 31,2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0324085	EM VEH P S LSC 20 3C	FOOT	1,523.000				
X8570226	FAC T4 CAB SPL	EACH	1.000				
X8570231	FAC T5 CAB SPL	EACH	1.000				
X8600105	MASTER CONTROLLER SPL	EACH	1.000				
X8620200	UNINTER POWER SUP SPL	EACH	2.000				
X8710024	FOCC62.5/125 MM12SM24	FOOT	632.000				
X8820010	TS BACKPLATE SPL	EACH	26.000				
Z0030850	TEMP INFO SIGNING	SQ FT	102.800				
Z0033056	OPTIM TRAF SIGNAL SYS	EACH	1.000				
Z0073510	TEMP TR SIGNAL TIMING	EACH	2.000				
*ADD 66900200	NON SPL WASTE DISPOSL	CU YD	30.000				
*ADD 66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				
*ADD 66900530	SOIL DISPOSAL ANALY	EACH	1.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60T79

State Job # - C-91-441-12

Project Number  
 ACHSIP-0347/029/

Route  
 FAP 347

County Name - DUPAGE - -

Code - 43 - -

District - 1 - -

Section Number - CY-TS-1 (12)

\*REVISED: OCTOBER 31,2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70100310	TRAF CONT-PROT 701421	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70102630	TR CONT & PROT 701601	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	6.000				
72000100	SIGN PANEL T1	SQ FT	62.500				
78008270	POLYUREA PM T1 LN 24	FOOT	362.000				
78300100	PAVT MARKING REMOVAL	SQ FT	750.000				
78300200	RAISED REF PVT MK REM	EACH	8.000				
80500020	SERV INSTALL POLE MT	EACH	2.000				
81028200	UNDRGRD C GALVS 2	FOOT	3,123.000				
81028210	UNDRGRD C GALVS 2 1/2	FOOT	437.000				
81028220	UNDRGRD C GALVS 3	FOOT	293.000				
81028240	UNDRGRD C GALVS 4	FOOT	1,230.000				
81400100	HANDHOLE	EACH	9.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60T79

State Job # - C-91-441-12

Project Number  
 ACHSIP-0347/029/

Route  
 FAP 347

County Name - DUPAGE - -

Code - 43 - -

District - 1 - -

Section Number - CY-TS-1 (12)

\*REVISED: OCTOBER 31,2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
81400200	HD HANDHOLE	EACH	6.000				
81400300	DBL HANDHOLE	EACH	6.000				
85000200	MAIN EX TR SIG INSTAL	EACH	1.000				
86400100	TRANSCEIVER - FIB OPT	EACH	2.000				
87300925	ELCBL C TRACER 14 1C	FOOT	632.000				
87301225	ELCBL C SIGNAL 14 3C	FOOT	1,523.000				
87301245	ELCBL C SIGNAL 14 5C	FOOT	7,955.000				
87301255	ELCBL C SIGNAL 14 7C	FOOT	924.000				
87301305	ELCBL C LEAD 14 1PR	FOOT	10,796.000				
87301790	ELCBL C SERV 2 2C	FOOT	642.000				
87301805	ELCBL C SERV 6 2C	FOOT	70.000				
87301900	ELCBL C EGRDC 6 1C	FOOT	2,177.000				
87502480	TS POST GALVS 14	EACH	2.000				
87502500	TS POST GALVS 16	EACH	2.000				
87700160	S MAA & P 24	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60T79

State Job # - C-91-441-12

Project Number  
 ACHSIP-0347/029/

Route  
 FAP 347

County Name - DUPAGE - -

Code - 43 - -

District - 1 - -

Section Number - CY-TS-1 (12)

\*REVISED: OCTOBER 31,2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
87700190	S MAA & P 30	EACH	2.000				
87700220	S MAA & P 36	EACH	2.000				
87703222	S MAA & P DMA 48 & 22	EACH	2.000				
87800100	CONC FDN TY A	FOOT	16.000				
87800150	CONC FDN TY C	FOOT	8.000				
87800400	CONC FDN TY E 30D	FOOT	47.000				
87800415	CONC FDN TY E 36D	FOOT	22.000				
87800420	CONC FDN TY E 42D	FOOT	30.000				
87900200	DRILL EX HANDHOLE	EACH	6.000				
88030020	SH LED 1F 3S MAM	EACH	24.000				
88030050	SH LED 1F 3S BM	EACH	6.000				
88030110	SH LED 1F 5S MAM	EACH	2.000				
88030240	SH LED 2F 1-3 1-5 BM	EACH	2.000				
88500100	INDUCTIVE LOOP DETECT	EACH	32.000				
88600100	DET LOOP T1	FOOT	1,849.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60T79

State Job # - C-91-441-12

Project Number  
 ACHSIP-0347/029/

Route  
 FAP 347

County Name - DUPAGE - -

Code - 43 - -

District - 1 - -

Section Number - CY-TS-1 (12)

\*REVISED: OCTOBER 31,2012

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
89000100	TEMP TR SIG INSTALL	EACH	2.000				
89501400	REL EM VEH PR SYS D U	EACH	6.000				
89501410	REL EM VEH PR SYS P U	EACH	2.000				
89502350	REM & RE ELCBL FR CON	FOOT	1,224.000				
89502375	REMOV EX TS EQUIP	EACH	2.000				
89502376	REBUILD EX HANDHOLE	EACH	2.000				
89502380	REMOV EX HANDHOLE	EACH	23.000				
89502385	REMOV EX CONC FDN	EACH	18.000				

POLYUREA PAVEMENT MARKINGS (BDE)..... 81  
PORTLAND CEMENT CONCRETE (BDE) ..... 81  
QUALITY CONTROL/QUALITY ASSURANCE OF CONCRETE MIXTURES (BDE) ..... 115  
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES ..... 128  
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE) ..... 131  
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 132  
TRACKING THE USE OF PESTICIDES (BDE)..... 132  
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) ..... 133  
UTILITY COORDINATION AND CONFLICTS (BDE)..... 133  
WEEKLY DBE TRUCKING REPORTS (BDE)..... 138  
WORKING DAYS (BDE) ..... 138

## REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES

Revise Article 669.01 of the Standard Specifications to read:

**“669.01 Description.** This work shall consist of the transportation and proper disposal of contaminated soil and water. This work shall also consist of the removal, transportation, and proper disposal of underground storage tanks (UST), their content and associated underground piping to the point where the piping is above the ground, including determining the content types and estimated quantities.”

Revise Article 669.08 of the Standard Specifications to read:

**“669.08 Contaminated Soil and/or Groundwater Monitoring.** The Contractor shall hire a qualified environmental firm to monitor the area containing the regulated substances. The affected area shall be monitored with a photoionization detector (PID) utilizing a lamp of 10.6eV or greater or a flame ionization detector (FID). Any field screen reading on the PID or FID in excess of background levels indicates the potential presence of contaminated material requiring handling as a non-special waste, special waste, or hazardous waste. No excavated soils can be taken to a clean construction and demolition debris (CCDD) facility or an uncontaminated soil fill operation with detectable PID or FID meter readings. The PID or FID meter shall be calibrated on-site and background level readings taken and recorded daily. All testing shall be done by a qualified engineer/technician. Such testing and monitoring shall be included in the work. The Contractor shall identify the exact limits of removal of non-special waste, special waste, or hazardous waste. All limits shall be approved by the Engineer prior to excavation. The Contractor shall take all necessary precautions.

Based upon PID or FID readings indicating contamination, a soil or groundwater sample shall be taken from the same location and submitted to an approved laboratory. Soil or groundwater samples shall be analyzed for the contaminants of concern, including pH, based on the property's land use history or the parameters listed in the maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605. The analytical results shall serve to document the level of soil contamination. Soil and groundwater samples may be required at the discretion of the Engineer to verify the level of soil and groundwater contamination.

Samples shall be grab samples (not combined with other locations). The samples shall be taken with disposable instruments. The samples shall be placed in sealed containers and transported in an insulated container to the laboratory. The container shall maintain a temperature of 39 °F (4 °C). All samples shall be clearly labeled. The labels shall indicate the sample number, date sampled, location and elevation, and any other observations.

The laboratory shall use a detectable concentration which is equal to the lowest appropriate practical quantitation limits (PQL) or estimated quantitation limit (EQL) specified in "Test Methods for Evaluating Solid Wastes, Physical/Chemical Methods", EPA Publication No. SW-846 and "Methods for the Determination of Organic Compounds in Drinking Water", EPA, EMSL, EPA-600/4-88/039. For parameters where the specified cleanup objective is below the acceptable detection limit (ADL), the ADL shall serve as the cleanup objective. For other parameters the ADL shall be equal to or below the specified cleanup objective.”

Replace the first two paragraphs of Article 669.09 of the Standard Specifications with the following:

**“669.09 Contaminated Soil and/or Groundwater Management and Disposal.** The management and disposal of contaminated soil and/or groundwater shall be according to the following:

- (a) Soil Analytical Results Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels exceed the most stringent maximum allowable concentration (MAC) for chemical constituents in uncontaminated soil established pursuant to Subpart F of 35 Illinois Administrative Code 1100.605, the soil shall be managed as follows:
  - (1) When analytical results indicate inorganic chemical constituents exceed the most stringent MAC but they are still considered within area background levels by the Engineer, the excavated soil can be utilized within the construction limits as fill, when suitable. Such soil excavated for storm



- sewers can be placed back into the excavated trench as backfill, when suitable, unless trench backfill is specified. If the soils cannot be utilized within the construction limits, they shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.
- (2) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for a Metropolitan Statistical Area (MSA) County, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
  - (3) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, or the MAC within the Chicago corporate limits, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago or within the Chicago corporate limits provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
  - (4) When analytical results indicate chemical constituents exceed the most stringent MAC but do not exceed the MAC for an MSA County excluding Chicago, the excavated soil can be utilized within the construction limits as fill, when suitable, or managed and disposed of off-site as "uncontaminated soil" at a CCDD facility or an uncontaminated soil fill operation within an MSA County excluding Chicago provided the pH of the soil is within the range of 6.25 - 9.0, inclusive.
  - (5) When the Engineer determines soil cannot be managed according to Articles 669.09(a)(1) through (a)(4) above, the soil shall be managed and disposed of off-site as a non-special waste, special waste, or hazardous waste as applicable.
- (b) Soil Analytical Results Do Not Exceed Most Stringent MAC. When the soil analytical results indicate that detected levels do not exceed the most stringent MAC but the pH of the soil is less than 6.25 or greater than 9.0, the excavated soil can be utilized within the construction limits or managed and disposed of off-site as "uncontaminated soil" according to Article 202.03. However the excavated soil cannot be taken to a CCDD facility or an uncontaminated soil fill operation.
- (c) Groundwater. When groundwater analytical results indicate the detected levels are above Appendix B, Table E of 35 Illinois Administrative Code 742, the most stringent Tier 1 Groundwater Remediation Objectives for Groundwater Component of the Groundwater Ingestion Route for Class 1 groundwater, the groundwater shall be managed off-site as a special waste.

All groundwater encountered within lateral trenches may be managed within the trench and allowed to infiltrate back into the ground. If the groundwater cannot be managed within the trench it must be removed as a special or hazardous waste. The Contractor is prohibited from managing groundwater within the trench by discharging it through any existing or new storm sewer. The Contractor shall install backfill plugs within the area of groundwater contamination.

One backfill plug shall be placed down gradient to the area of groundwater contamination. Backfill plugs shall be installed at intervals not to exceed 50 ft (15 m). Backfill plugs are to be 4 ft (1.2 m) long, measured parallel to the trench, full trench width and depth. Backfill plugs shall not have any fine aggregate bedding or backfill, but shall be entirely cohesive soil or any class of concrete. The Contractor shall provide test data that the material has a permeability of less than  $10^{-7}$  cm/sec according to ASTM D 5084, Method A or per another test method approved by the Engineer."

Revise Article 669.14 of the Standard Specifications to read:

**“669.14 Final Environmental Construction Report.** At the end of the project, the Contractor will prepare and submit three copies of the Environmental Construction Report on the activities conducted during the life of the project, one copy shall be submitted to the Resident Engineer, one copy shall be submitted to the District's Environmental Studies Unit, and one copy shall be submitted with an electronic copy in Adode.pdf format to the Geologic and Waste Assessment Unit, Bureau of Design and Environment, IDOT, 2300 South

Dirksen Parkway, Springfield, Illinois 62764. The technical report shall include all pertinent information regarding the project including, but not limited to:

- (a) Measures taken to identify, monitor, handle, and dispose of soil or groundwater containing regulated substances, to prevent further migration of regulated substances, and to protect workers,
- (b) Cost of identifying, monitoring, handling, and disposing of soil or groundwater containing regulated substances, the cost of preventing further migration of regulated substances, and the cost for worker protection from the regulated substances. All cost should be in the format of the contract pay items listed in the contract plans (identified by the preliminary environmental site investigation (PESA) site number),
- (c) Plan sheets showing the areas containing the regulated substances,
- (d) Field sampling and testing results used to identify the nature and extent of the regulated substances,
- (e) Waste manifests (identified by the preliminary environmental site investigation (PESA) site number) for special or hazardous waste disposal, and
- (f) Landfill tickets (identified by the preliminary environmental site investigation (PESA) site number) for non-special waste disposal.”

Revise the second paragraph of Article 669.16 of the Standard Specifications to read:

“The transportation and disposal of soil and other materials from an excavation determined to be contaminated will be paid for at the contract unit price per cubic yard (cubic meter) for NON-SPECIAL WASTE DISPOSAL, SPECIAL WASTE DISPOSAL, or HAZARDOUS WASTE DISPOSAL.”

Qualifications. The term environmental firm shall mean an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is pre-qualified in hazardous waste by the Department. Documentation includes but not limited to verifying remediation and special waste operations for sites contaminated with gasoline, diesel, or waste oil in accordance with all Federal, State, or local regulatory requirements and shall be provided to the Engineer for approval. The environmental firm selected shall not be a former or current consultant or have any ties with any of the properties contained within and/or adjacent to this construction project.

General. This Special Provision will likely require the Contractor to subcontract for the execution of certain activities.

All contaminated materials shall be managed as either “uncontaminated soil” or non-special waste. This work shall include monitoring and potential sampling, analytical testing, and management of a material contaminated by regulated substances. The Environmental Firm shall continuously monitor all soil excavation for worker protection and soil contamination. **Phase I Preliminary Engineering information is available through the District’s Environmental Studies Unit.** Soil samples or analysis without the approval of the Engineer will be at no additional cost to the Department. The lateral distance is measured from centerline and the farthest distance is the offset distance or construction limit whichever is less.

The Contractor shall manage any excavated soils and sediment within the following areas:

- Station 728+25 to Station 728+70 0 to 100 feet LT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(3) and shall be managed in accordance to Article 669.09.
- Station 728+70 to Station 730+00 0 to 80 feet LT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: Arsenic.
- Station 728+25 to Station 729+00 0 to 60 feet RT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(3) and shall be managed in accordance to Article 669.09.

- Station 728+70 to Station 729+15 60 to 100 feet RT (Utility Corridor, PESA Site 2497-5, 900 block of Roosevelt Road). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: Arsenic.
- Station 729+40 to Station 730+10 0 to 110 feet RT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(1) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: Arsenic.
- Station 729+40 to Station 729+70 140 to 170 feet RT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(2) and shall be managed in accordance to Article 669.09.
- Station 733+50 to Station 737+50 0 to 130 feet LT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(5) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: Methylene Chloride, Manganese, and Arsenic.
- Station 733+50 to Station 734+00 0 to 110 feet RT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(3) and shall be managed in accordance to Article 669.09.
- Station 735+00 to Station 735+40 70 to 110 feet RT (IDOT I-355 ROW, PESA Site 2497-6, 900 and 1000 blocks of Roosevelt Road). This material meets the criteria of Article 669.09(a)(5) and shall be managed in accordance to Article 669.09. Contaminants of concern sampling parameters: Arsenic.

P:\My Documents\IDOT\IDOT\Districts\Distr1\PSI\EE7\24sp ee7.docx  
rev November 1, 2012

## REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)

Effective: November 2, 2012

Revise the first four paragraphs of Article 202.03 of the Standard Specifications to read:

**“202.03 Removal and Disposal of Surplus, Unstable, Unsuitable, and Organic Materials.** Suitable excavated materials shall not be wasted without permission of the Engineer. The Contractor shall dispose of all surplus, unstable, unsuitable, and organic materials, in such a manner that public or private property will not be damaged or endangered.

Suitable earth, stones and boulders naturally occurring within the right-of-way may be placed in fills or embankments in lifts and compacted according to Section 205. Broken concrete without protruding metal bars, bricks, rock, stone, reclaimed asphalt pavement with no expansive aggregate, or uncontaminated dirt and sand generated from construction or demolition activities may be used in embankment or in fill. If used in fills or embankments, these materials shall be placed and compacted to the satisfaction of the Engineer; shall be buried under a minimum of 2 ft (600 mm) of earth cover (except when the materials include only uncontaminated dirt); and shall not create an unsightly appearance or detract from the natural topographic features of an area. Broken concrete without protruding metal bars, bricks, rock, or stone may be used as riprap as approved by the Engineer. If the materials are used for fill in locations within the right-of-way but outside project construction limits, the Contractor must specify to the Engineer, in writing, how the landscape restoration of the fill areas will be accomplished. Placement of fill in such areas shall not commence until the Contractor's landscape restoration plan is approved by the Engineer.