


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				HBP/TBP FUNDS		
				80% FED 20% LOCAL	80% FED 20% LOCAL	80% FED 20% LOCAL
				ROADWAY	BRIDGE	TRAINEES
				0004	0011	0042
				URBAN	URBAN	URBAN
28200200	FILTER FABRIC	SQ YD	86	16	70	
30300124	AGGREGATE SUBGRADE IMPROVEMENT 24"	SQ YD	1,775	1,775		
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1,120	1,120		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	259	259		
40600300	AGGREGATE (PRIME COAT)	TON	4	4		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160		
40701801	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 6"	SQ YD	1,775	1,775		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	534	534		
44000100	PAVEMENT REMOVAL	SQ YD	2,556	2,556		
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	144	144		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	974	974		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50105220	PIPE CULVERT REMOVAL	FOOT	94	94		
50200100	STRUCTURE EXCAVATION	CU YD	75		75	
50200300	COFFERDAM EXCAVATION	CU YD	43		43	
50201101	COFFERDAM (TYPE 1) (LOCATION - 1)	EACH	1		1	
50201102	COFFERDAM (TYPE 1) (LOCATION - 2)	EACH	1		1	
50300225	CONCRETE STRUCTURES	CU YD	70		70	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	107		107	
50300260	BRIDGE DECK GROOVING	SQ YD	583		583	
50300280	CONCRETE ENCASEMENT	CU YD	19		19	
50300300	PROTECTIVE COAT	SQ YD	683		683	
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ FT	3,981		3,981	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	40,810		40,810	

▲ SPECIALTY ITEMS

FILE NAME = S:\JUL16800-6899\6842\067\Micros\0400 Sheets\01-63666-wht-500.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = dennis
PLOT SCALE = 1/8" = 1.0000' / IN.
PLOT DATE = 8/23/22.2

DESIGNED - VLM
DRAWN - DJW
CHECKED - AJS
DATE - 4-23-12

REVISED -
REVISED -
REVISED -
REVISED -

MCHENRY COUNTY DIVISION OF TRANSPORTATION
HILL ROAD BRIDGE OVER
NORTH BRANCH NIPPERSINK CREEK

SUMMARY OF QUANTITIES
SCALE: AS SHOWN SHEET NO. OF SHEETS STA. TO STA.

TR	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
21	08-00356-00-BR	MCHENRY	77	5
			CONTRACT NO. 63666	

FED. ROAD DIST. NO. 1 ILLINOIS FED. RD. PROJECT