


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	LAWRENCE ROAD		
				ROADWAY 0004	BRIDGE REPLACEMENT 0011	MCHENRY COUNTY (NON-PARTICIPATING)
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,354	2,354		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	350	350		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,446	1,446		
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1			1
* 81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	60			60
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	55			55
* 81603115	UNIT DUCT, 600V, 3-1C NO.1, 1/C NO.1 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	50			50
X0426200	DEWATERING	L SUM	1	1		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	467	365	102	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	3	3		
* X6310088	TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL)	EACH	2	2		
X6650206	WOVEN WIRE FENCE TO BE REMOVED AND RE-ERECTED	FOOT	85	85		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
X7240300	SIGN REMOVAL	EACH	10	10		
XX005968	TURBIDITY CURTAIN	SQ YD	99	99		
XX008458	CONCRETE WEARING SURFACE (VARIABLE DEPTH)	CU YD	90		90	
* XX008696	PROCUREMENT AND INSTALLATION OF RWIS	L SUM	1			1
* Z0007124	STEEL RAILING (SPECIAL)	FOOT	210		210	
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	91	91		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0026407	TEMPORARY SHEET PILING	SQ FT	1,747		1,747	
Z0030275	IMPACT ATTENUATORS, TEMPORARY (SEVERE USE,NARROW), TEST LEVEL 2	EACH	2	2		
Z0030355	IMPACT ATTENUATORS, RELOCATE (SEVERE USE), TEST LEVEL 2	EACH	2	2		
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	52	52		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	145		145	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	742	742		
△ Z0076600	TRAINEES	HOUR	500 △	500		
△ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	500 △	500		

* SPECIALTY ITEMS

△ CONSTRUCTION TYPE - CODE 0042

FILE NAME: \\V755-012 Lawrence Phase II\CADD SHEETS\758 02-int-500.dwg



USER NAME = gellwanger	DESIGNED - GJE	REVISED -
PLOT SCALE = 20.0000' / 1" =	DRAWN - GJE	REVISED -
PLOT DATE = 8/29/2012	CHECKED - CF	REVISED -
	DATE - 08/17/12	REVISED -

**MCHENRY COUNTY
DIVISION OF TRANSPORTATION**

**LAWRENCE ROAD BRIDGE OVER PISCASAW CREEK
SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 5 OF 87 SHEETS STA. TO STA.

F.A.S. RTE. 0028	SECTION 08-00355-01-BR	COUNTY MCHENRY	TOTAL SHEETS 87	SHEET NO. 5
CONTRACT NO. 63694			ILLINOIS FED. AID PROJECT	