

TRAFFIC CONTROL NOTES

1. SIDEWALK AND DRIVEWAY REMOVAL AND INSTALLATION SHALL BE LIMITED TO WORK ON ONE SIDE OF THE STREET IN EACH DIRECTION AND THREE BLOCKS AT A TIME TO MINIMIZE CONGESTION, OR AS APPROVED BY THE ENGINEER.
2. ALL STREETS SHALL ALL BE MAINTAINED AS DIRECTED BY THE ENGINEER.
3. THE ENGINEER SHALL BE INFORMED 48 HOURS IN ADVANCE OF ANY CHANGE IN CONSTRUCTION STAGING.
4. THE CONTRACTOR SHALL PROVIDE AND INSTALL TWO (2) WEIGHTED SAND BAGS ON EACH TYPE I OR TYPE II BARRICADE USED.
5. LANE CLOSURES ON OAKTON STREET WILL ONLY BE PERMITTED BETWEEN THE HOURS OF 9AM AND 3PM. ALL LANE CLOSURES SHALL BE APPROVED BY THE ENGINEER.
6. TYPE I BARRICADES AND VERTICAL PANELS SHALL BE EQUIPPED WITH MONO-DIRECTIONAL STEADY BURN LIGHTS AND SHALL BE PLACED AT 50' MAXIMUM INTERVALS ALONG THE PROPOSED WORK ZONE AND MAXIMUM 25' WITHIN TAPERED SECTIONS OR AS DIRECTED BY THE ENGINEER.
7. AT LEAST 48 HOUR NOTICE SHALL BE PROVIDED TO THE COOK COUNTY PERMIT DIVISION, MR. BHANU VYAS (312) 603-1670 BEFORE BEGINNING WORK.

HIGHWAY STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
424001-06	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
424006	DIAGONAL CURB RAMPS FOR SIDEWALKS
424011	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
701606-08	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-08	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701801-05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
701901-02	TRAFFIC CONTROL DEVICES
720006-03	SIGN PANEL ERECTION DETAILS
814001-02	HANDHOLES
814006-02	DOUBLE HANDHOLES
836001-01	LIGHT POLE FOUNDATION

COMMITMENTS

WORK ON THIS CONTRACT WILL NOT BEGIN PRIOR TO APRIL 1, 2013.

TREE LEGEND

KC	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 3" CALIPER, BALLED AND BURLAPPED
TCH	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 3" CALIPER, BALLED AND BURLAPPED
CSL	TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 3" CALIPER, TREE FORM, BALLED AND BURLAPPED
AGG	TREE, GINKGO BILOBA AUTUMN GOLD (AUTUMN GOLD GINKGO), 3" CALIPER, BALLED AND BURLAPPED
PSG	TREE, GINKGO BILOBA PRINCETON SENTRY (PRINCETON SENTRY GINKGO), 3" CALIPER, BALLED AND BURLAPPED
NHE	TREE, ULMAS CARPINIFOLIA NEW HORIZON (NEW HORIZON SMOOTHLEAF ELM), 3" CALIPER, BALLED AND BURLAPPED

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	INDEX OF SHEETS, HIGHWAY STANDARDS, TRAFFIC CONTROL NOTES, BENCHMARKS, TREE LEGEND AND COMMITMENTS
3	GENERAL NOTES
4 - 6	SUMMARY OF QUANTITIES
7	TYPICAL SECTIONS AND HOT-MIX ASPHALT MIXTURE REQUIREMENTS
8 - 9	SCHEDULE OF QUANTITIES
10	PLAN: E. OAKTON STREET STA 9+00 TO STA 19+50
11	PLAN: E. OAKTON STREET STA 19+50 TO STA 30+50
12	PLAN: E. OAKTON STREET STA 30+50 TO STA 42+50
13 - 14	STREET LIGHTING - SINGLE LINE DIAGRAM
15	STREET LIGHTING PLAN: E. OAKTON STREET STA 9+00 TO STA 19+50
16	STREET LIGHTING PLAN: E. OAKTON STREET STA 19+50 TO STA 30+50
17	STREET LIGHTING PLAN: E. OAKTON STREET STA 30+50 TO STA 42+50
18 - 21	STREET LIGHTING DETAILS
23 - 24	DETAILS
25	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
26	LIGHT POLE FOUNDATION OFFSET
27	(TC-10) TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS
28	(TC-18) SIGNING FOR FLAGGING OPERATIONS AT WORK ZONE OPENINGS
29	(TC-22) ARTERIAL ROAD INFORMATION SIGNING

BENCHMARKS

BM #1	ARROW BOLT @ NW CORNER OF TRIPP AVE. AND OAKTON ST. ELEV. = 607.01
BM #2	LOCATED WITHIN THE TRAFFIC ISLAND @ THE NW CORNER OF OAKTON ST. AND SKOKIE BLVD. SK318 ELEV. = 611.06
BM #3	NE CORNER OF KNOX AVE. AND OAKTON ST. W. FLANGE BOLT ELEV. = 608.56
BM #5	SE FLANGE BOLT NE CORNER OF KILBOURN AVE. AND OAKTON ST. ELEV. = 609.71
BM #7	SK311 LOCATED @ THE NW CORNER OF OAKTON ST. AND KOSTNER AVE. ELEV. = 606.27
BM #13	SOUTH SIDE OF KILPATRICK AVE. AND OAKTON ST. ARROW BOLT ELEV. = 609.73
BM #14	SW CORNER OF KENTON AVE. AND OAKTON ST. ARROW BOLT ELEV. = 610.81
BM #15	W. BOLT ON TOP OF FH @ SW CORNER OF KILDARE AVE AND OAKTON ST. ELEV. = 608.14

CONFIDENTIAL - 2013 BY BAXTER & WOODMAN, INC. ALL RIGHTS RESERVED. NO PART OF THIS DOCUMENT IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM. PROJECT NO. 11-00286-00-15. DATE: 4/10/2013. 5:00 PM.



DESIGNED	- DSH	REVISED	- 6-3-12 PER IDOT
DRAWN	- MAC	REVISED	-
CHECKED	- MDW	REVISED	-
DATE	- 5-14-12	FILE	- 100751-Gen-note.sht

VILLAGE OF SKOKIE, ILLINOIS
F.A.U. ROUTE 1332 E. OAKTON STREET
FROM F.A.P. 350 U.S. ROUTE 41 (SKOKIE BOULEVARD) TO LOWELL AVENUE
STREETScape IMPROVEMENTS

INDEX OF SHEETS, HIGHWAY STANDARDS, TRAFFIC CNTRL
NOTES, BENCHMARKS, TREE LEGEND AND COMMITMENTS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1332	11-00286-00-15	COOK	29	2
C-91-149-12		CONTRACT NO. 63737		
FED. ROAD DIST. NO. 1 (ILLINOIS)		FED. AID PROJECT: TE-00016891		

SCALE: NONE STA. TO STA.