

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0005
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	542	542
	25200200	SUPPLEMENTAL WATERING	UNIT	2	2
	28000510	INLET FILTERS	EACH	5	5
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	130	130
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2710	2710
	40600300	AGGREGATE (PRIME COAT)	TON	28	28
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10
	40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	586	586
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	262	262
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1171	1171
	42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	41	41
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	800	800
	42400800	DETECTABLE WARNINGS	SQ FT	156	156
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	13528	13528
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	293	293
	44000600	SIDEWALK REMOVAL	SQ FT	800	800
	44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	4	4
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	81	81
	44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	76	76
	44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	1641	1641
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	5	5
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3
	67100100	MOBILIZATION	L SUM	1	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1

* - INDICATES SPECIALTY ITEMS

SUMMARY OF QUANTITIES					CONSTRUCTION TYPE CODE
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	0005
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	905	905
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175
	X2520700	SODDING, SPECIAL	SQ YD	542	542
	XX004847	STONE DRIVEWAY REMOVAL	SQ YD	23	23
	XX008200	STABILIZED DRIVEWAY PAVEMENT	SQ YD	275	275
	Z0004562	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2500	2500

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ETC. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.

FILE NAME = 11999-QUAN01 - QUAN P01

USER NAME =	DESIGNED -	REVISED -
	CHECKED - TAG	REVISED -
PLOT SCALE =	DRAWN - MED	REVISED -
PLOT DATE = 08-10-12	CHECKED - AG	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

223RD STREET RESURFACING
NICHOLS DR TO MURPHY AVE
SUMMARY OF QUANTITIES & GENERAL NOTES

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1041	11-00030-00-RS	COOK	10	2
CONTRACT NO. 63739				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003 (914)				

SCALE: NONE SHEET NO. 2 OF 10 SHEETS STA. TO STA.