

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE ROADWAY 0004 RURAL	80% FED 20% STATE BRIDGE 0014 SN 089-0007
20200100	EARTH EXCAVATION	CU YD	515	515	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	105	105	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	406	406	
△ 25000750	MOWING	ACRE	.25	.25	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	406	406	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50	
28000400	PERIMETER EROSION BARRIER	FOOT	629	629	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	824	824	
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	525	525	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	11	11	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	168	168	
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	611	611	
42100615	PAVEMENT REINFORCEMENT	SQ YD	611	611	
44000100	PAVEMENT REMOVAL	SQ YD	588	588	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,268	1,268	

△ SPECIALTY ITEM      △ 100% STATE ONLY

FILE NAME = s:\p1\12328-5399-5345\2012\mtrca\load sheet\0204E76-shr-500.dgn

**SA**  
1170 SOUTH HOUBOLT ROAD  
JOLIET, ILLINOIS 60431  
**STRAND**  
ASSOCIATES\*  
(815) 744-4200

USER NAME = brianf	DESIGNED - EMD	REVISED -
PLLOT SCALE = 20.0000' / IN.	DRAWN - BJF	REVISED -
PLLOT DATE = 6/6/2012	CHECKED - VLF	REVISED -
	DATE - 02/29/12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: AS SHOWN	SHEET	OF	SHEETS	STA.	TO STA.
-----------------	-------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5	(19VB-1)D	STEPHENSON	73	4
CONTRACT NO. 64E76				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				