


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				80% FED 20% STATE ROADWAY 0004 RURAL	80% FED 20% STATE BRIDGE 0014 SN 089-0007
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	150	150	
44004250	PAVED SHOULDER REMOVAL	SQ YD	368	368	
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	499	499	
50102400	CONCRETE REMOVAL	CU YD	52		52
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1
50157300	PROTECTIVE SHIELD	SQ YD	655		655
50200100	STRUCTURE EXCAVATION	CU YD	353		353
50300100	FLOOR DRAINS	EACH	10		10
50300225	CONCRETE STRUCTURES	CU YD	120		120
50300255	CONCRETE SUPERSTRUCTURE	CU YD	715		715
50300260	BRIDGE DECK GROOVING	SQ YD	2,083		2,083
50300300	PROTECTIVE COAT	SQ YD	2,382		2,382
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	6,804		6,804
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	179,780		179,780

* SPECIALTY ITEM  100% STATE ONLY

FILE NAME = s:\p1\15389-6399\6345\029\mstron\asdd sheet\0204E76-hi-500.dgn



USER NAME * brianf	DESIGNED - EMD	REVISED -
PLOT SCALE * 20.0000' / IN.	DRAWN - B.J.F.	REVISED -
PLOT DATE * 8/6/2012	CHECKED - V.L.F.	REVISED -
	DATE - 02/29/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET	OF	SHEETS
AS SHOWN			

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5	(19VB-1)D	STEPHENSON	73	5
CONTRACT NO. 64E76				
FED. ROAD DIST. NO. 2 [ILLINOIS] FED. AID PROJECT				