

	LOCATION		EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT TO STAY ON SITE	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	
	STA.	STA.	CU YD	CU YD	CU YD	CU YD	
STAGE 1	428+50	428+85	8.16	6.12	1.85	4.27	
	428+85	429+00	6.39	4.79	1.58	3.21	
	429+00	429+50	48.91	36.68	8.14	28.54	
	429+50	429+78	44.92	33.69	4.44	29.25	
	429+78	430+00	17.97	13.48	1.09	12.38	
	BRIDGE OMISSION						
	432+00	432+43	6.60	4.95	12.18	-7.23	
	432+43	432+50	2.44	1.83	2.16	-0.33	
	432+50	433+00	51.09	38.32	1.13	37.19	
	433+00	433+50	85.86	64.39	0.65	63.75	
STAGE 2	433+50	433+77	29.83	22.38	0.35	22.02	
	433+77	434+00	5.21	3.91	0.21	3.70	
	429+47	429+50	2.46	1.84	0.28	1.56	
	429+50	430+00	70.40	52.80	2.20	50.60	
	430+00	430+50	41.67	31.25	4.70	26.55	
	430+50	430+70	4.03	3.02	3.34	-0.31	
	430+70	431+00	2.34	1.75	2.69	-0.94	
	BRIDGE OMISSION						
	433+00	433+31	21.97	16.48	2.38	14.10	
	433+31	433+50	25.73	19.30	2.45	16.85	
433+50	434+00	34.48	25.86	5.22	20.64		
434+00	434+27	0.00	0.00	5.18	-5.18		
434+27	434+50	0.00	0.00	3.30	-3.30		
TOTAL:			515.00	385.00	70.00	320.00	

20200100		EARTH EXCAVATION	
CU YD	LOCATION		QUANTITY
US BUS 20			
	STA. 428+50.00 TO 430+00.00	LT	126.35
BRIDGE OMISSION			
	STA. 432+00.00 TO 434+00.00	LT	181.03
	STA. 429+46.51 TO 431+00.00	RT	120.89
BRIDGE OMISSION			
	STA. 433+00.00 TO 434+50.00	RT	82.18
TOTAL:			515.00 CU YD

20201200		REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	
CU YD	LOCATION	DEPTH (IN)	QUANTITY
US BUS 20			
	STA. 428+50.00 TO 430+00.00	LT	6.00 25.72
BRIDGE OMISSION			
	STA. 432+00.00 TO 434+00.00	LT	6.00 31.21
	STA. 429+46.51 TO 431+00.00	RT	6.00 25.23
BRIDGE OMISSION			
	STA. 433+00.00 TO 434+00.00	RT	6.00 20.57
TOTAL:			105.00 CU YD

21101615		TOPSOIL FURNISH AND PLACE, 4"	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 428+50.00 TO 429+78.12	LT	127.55
BRIDGE OMISSION			
	STA. 432+00.00 TO 433+77.01	LT	138.39
	STA. 429+46.51 TO 431+00.00	RT	69.70
BRIDGE OMISSION			
	STA. 433+00.00 TO 434+50.00	RT	70.00
TOTAL:			406.00 SO YD

25000750		MOWING	
ACRE	LOCATION		QUANTITY
US BUS 20			
	STA. 428+50.00 TO 430+00.00	LT	0.03
BRIDGE OMISSION			
	STA. 432+00.00 TO 434+00.00	LT	0.03
	STA. 429+46.51 TO 431+00.00	RT	0.01
BRIDGE OMISSION			
	STA. 433+00.00 TO 434+50.00	RT	0.01
TOTAL:			0.25 ACRE

25100635		HEAVY DUTY EROSION CONTROL BLANKET	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 428+50.00 TO 430+00.00	LT	127.55
BRIDGE OMISSION			
	STA. 432+00.00 TO 434+00.00	LT	138.39
	STA. 429+46.51 TO 431+00.00	RT	69.70
BRIDGE OMISSION			
	STA. 433+00.00 TO 434+50.00	RT	70.00
TOTAL:			406.00 SO YD

28000250		TEMPORARY EROSION CONTROL SEEDING	
POUND	LOCATION	AREA	QUANTITY
US BUS 20			
	STA. 428+50.00 TO 430+00.00	LT	0.03 2.64
BRIDGE OMISSION			
	STA. 432+00.00 TO 434+00.00	LT	0.03 2.86
	STA. 429+46.51 TO 431+00.00	RT	0.01 1.44
BRIDGE OMISSION			
	STA. 433+00.00 TO 434+50.00	RT	0.01 1.45
TOTAL:			50.00 POUND

28000400		PERIMETER EROSION BARRIER	
FOOT	LOCATION		QUANTITY
US BUS 20			
	STA. 428+85.26 TO 428+85.26	LT	17.50
	STA. 428+85.26 TO 429+00.00	LT	14.82
	STA. 429+00.00 TO 429+50.00	LT	50.04
	STA. 429+50.00 TO 429+78.24	LT	28.25
	STA. 429+78.24 TO 430+07.88	LT	30.09
	STA. 429+46.52 TO 429+46.52	RT	9.40
	STA. 429+46.52 TO 430+00.00	RT	53.64
	STA. 430+00.00 TO 430+50.00	RT	50.01
	STA. 430+50.00 TO 431+00.77	RT	50.78
	STA. 432+09.79 TO 432+42.78	LT	36.36
	STA. 432+42.78 TO 432+50.00	LT	16.74
	STA. 432+50.00 TO 433+00.03	LT	50.14
	STA. 433+00.03 TO 433+77.01	LT	76.98
	STA. 433+77.01 TO 433+77.01	LT	7.90
	STA. 433+02.74 TO 433+31.47	RT	28.90
	STA. 433+31.47 TO 433+50.00	RT	18.53
	STA. 433+50.00 TO 434+00.00	RT	50.00
	STA. 434+00.00 TO 434+27.05	RT	27.19
	STA. 434+27.05 TO 434+27.05	RT	11.00
TOTAL:			629.00 FOOT

31100910		SUBBASE GRANULAR MATERIAL, TYPE A 12"	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 428+85.25 TO 429+35.05	LT	61.45
	STA. 429+35.05 TO 429+78.12	LT	47.04
	STA. 432+42.77 TO 433+04.25	LT	67.15
	STA. 433+04.25 TO 433+77.01	LT	87.47
	STA. 429+50.00 TO 429+62.22	LT/RT	76.71
	STA. 429+62.22 TO 430+42.40	LT/RT	251.68
	STA. 432+77.20 TO 433+49.03	LT/RT	225.47
	STA. 433+49.03 TO 433+50.00	LT/RT	6.09
TOTAL:			824.00 SO YD

31200500		STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 429+50.00 TO 429+62.22	LT/RT	75.36
	STA. 429+62.22 TO 430+34.08	LT/RT	221.57
	STA. 432+77.20 TO 433+49.03	LT/RT	221.48
	STA. 433+49.03 TO 433+50.00	LT/RT	5.98
TOTAL:			525.00 SO YD

40600625		LEVELING BINDER (MACHINE METHOD), N50	
TON	LOCATION	WIDTH (FT)	AREA (SQ YD)
US BUS 20			
	STA. 433+50.00 TO 433+75.00	54.00	150.00
TOTAL:			11.00 TON

40603310		HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	
TON	LOCATION	WIDTH (FT)	AREA (SQ YD)
US BUS 20			
	STA. 428+85.25 TO 429+35.05	9.11	50.38
	STA. 429+35.05 TO 429+78.12	7.83	37.47
	STA. 432+42.77 TO 433+04.25	8.83	60.32
	STA. 433+04.25 TO 433+77.01	9.82	79.39
	STA. 429+46.51 TO 430+26.45	8.83	78.43
	STA. 430+26.45 TO 430+69.61	7.84	37.60
	STA. 433+31.46 TO 433+74.75	7.84	37.71
	STA. 433+74.75 TO 434+27.04	8.71	50.63
	STA. 433+50.00 TO 433+75.00	54.00	150.00
	STA. 411+30.00 TO 425+66.00	2.00	319.11
	STA. 426+79.50 TO 430+71.92	2.00	87.20
	STA. 433+07.46 TO 443+30.00	2.00	227.23
	STA. 415+00.00 TO 428+85.04	2.00	307.79
	STA. 433+77.01 TO 448+45.00	2.00	326.22
TOTAL:			168.00 TON

42001420		BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 429+50.00 TO 430+06.48		338.85
	STA. 433+04.82 TO 433+50.00		271.23
TOTAL:			611.00 SO YD

42100615		PAVEMENT REINFORCEMENT	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 429+50.00 TO 430+06.48		338.85
	STA. 433+04.82 TO 433+50.00		271.23
TOTAL:			611.00 SO YD

44000100		PAVEMENT REMOVAL	
SO YD	LOCATION		QUANTITY
US BUS 20			
	STA. 429+50.00 TO 430+06.48		326.32
	STA. 433+04.82 TO 433+50.00		261.05
TOTAL:			588.00 SO YD

FILE NAME = s:\p1\6380--6395\6346\025\micro\Acadd sheets\0264E76-sh1-Schedule.dgn



1170 SOUTH HOUBOLT ROAD
JOLIET, ILLINOIS 60431
(815) 744-4200

USER NAME = brianf
DESIGNED - EMD
DRAWN - BJF
CHECKED - VLF
DATE - 02/29/12

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SCALE: AS SHOWN SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5	(19VB-1D)	STEPHENSON	73	13
CONTRACT NO. 64E76				

FED. ROAD DIST. NO. 2 (ILLINOIS) FED. AID PROJECT