

SO_YD	LOCATION	WIDTH (FT)	QUANTITY
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"		
	US BUS 20		
	STA. 411+30.00 TO 425+66.00	2.00 RT	319.11
	STA. 426+79.50 TO 430+71.92	2.00 RT	87.20
	STA. 433+07.46 TO 443+30.00	2.00 RT	227.23
	STA. 415+00.00 TO 428+85.04	2.00 LT	307.79
	STA. 433+77.01 TO 448+45.00	2.00 LT	326.22
	<b>TOTAL:</b>		<b>1268.00 SO YD</b>

FOOT	LOCATION	QUANTITY
63200310	GUARDRAIL REMOVAL	
	US BUS 20	
	STA. 428+85.25 TO 430+03.20	LT 117.95
	STA. 429+46.51 TO 430+81.67	RT 135.16
	STA. 432+28.75 TO 433+77.01	LT 148.26
	STA. 433+07.62 TO 434+27.04	RT 119.42
	<b>TOTAL:</b>	<b>521.00 FOOT</b>

EACH	LOCATION	QUANTITY
70103815	TRAFFIC CONTROL SURVEILLANCE	
	US BUS 20	
	STA. 406+50.00 TO 456+50.00	5
	<b>TOTAL:</b>	<b>5.00 CAL DA</b>

SO_YD	LOCATION	WIDTH (FT)	QUANTITY
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"		
	US BUS 20		
	STA. 433+50.00 TO 433+75.00	54.00 LT/RT	150.00
	<b>TOTAL:</b>		<b>150.00 SO YD</b>

FOOT	LOCATION	QUANTITY
64200108	SHOULDER RUMBLE STRIPS, 8 INCH	
	US BUS 20	
	STA. 411+30.00 TO 425+66.00	RT 1436.00
	STA. 426+79.50 TO 430+71.92	RT 392.42
	STA. 433+07.46 TO 443+30.00	RT 1022.54
	STA. 415+00.00 TO 430+00.00	LT 1500.00
	STA. 433+09.42 TO 448+45.00	LT 1535.58
	<b>TOTAL:</b>	<b>5887.00 FOOT</b>

FOOT	LOCATION	OFFSET	OFFSET	LOCATION	COLOR	QUANTITY
70300100	SHORT TERM PAVEMENT MARKING					
	US BUS 20					
	STA. 415+00.00	26.00	TO 448+45.00	26.00	LT	SOLID WHITE 334.50
	STA. 411+11.52	26.00	TO 443+30.00	26.00	RT	SOLID WHITE 321.85
	STA. 412+90.10	2.00	TO 423+80.23	2.00	RT	SOLID YELLOW 43.61
	STA. 425+00.00	2.00	TO 427+11.45	2.00	RT	SOLID YELLOW 8.46
	STA. 418+50.00	2.00	TO 424+13.40	2.00	LT	SOLID YELLOW 22.54
	STA. 437+18.73	2.00	TO 455+05.00	2.00	RT	SOLID YELLOW 71.45
	STA. 425+00.00	2.00	TO 427+11.45	2.00	LT	SOLID YELLOW 8.46
	STA. 438+32.75	2.00	TO 451+66.72	2.00	LT	SOLID YELLOW 53.36
	STA. 405+00.00	14.00	TO 410+22.83	14.67	RT	WHITE DASHED 52.29
	STA. 423+89.87	14.00	TO 437+10.54	14.00	RT	WHITE DASHED 132.07
	STA. 450+28.85	14.00	TO 456+50.00	14.00	RT	WHITE DASHED 62.12
	STA. 423+91.77	14.00	TO 438+69.05	14.00	LT	WHITE DASHED 147.73
	STA. 448+75.74	13.00	TO 455+05.00	13.45	LT	WHITE DASHED 62.93
	<b>TOTAL:</b>					<b>1322.00 FOOT</b>

SO_YD	LOCATION	WIDTH (FT)	QUANTITY
44004250	PAVED SHOULDER REMOVAL		
	US BUS 20		
	STA. 428+85.03 TO 429+78.12	7.62 LT	76.83
	STA. 432+42.77 TO 433+48.34	6.27 LT	107.87
	STA. 429+63.95 TO 430+69.61	6.34 RT	92.79
	STA. 433+31.46 TO 434+25.49	8.44 RT	89.71
	<b>TOTAL:</b>		<b>368.00 SO YD</b>

EACH	LOCATION	QUANTITY
66700305	PERMANENT SURVEY MARKERS, TYPE II	
	US BUS 20	
	STA. 428+85.25 TO 434+27.04	1
	<b>TOTAL:</b>	<b>1.00 EACH</b>

SO_YD	LOCATION	WIDTH (FT)	QUANTITY
48203021	HOT-MIX ASPHALT SHOULDERS, 6"		
	US BUS 20		
	STA. 428+85.25 TO 429+35.05	9.83 LT	61.48
	STA. 429+35.05 TO 429+78.12	8.83 LT	44.65
	STA. 432+42.77 TO 432+85.82	8.83 LT	42.24
	STA. 432+85.82 TO 433+77.01	11.97 LT	105.38
	STA. 429+46.51 TO 430+26.46	8.83 RT	91.54
	STA. 430+26.46 TO 430+69.61	8.83 RT	42.33
	STA. 433+31.46 TO 433+74.75	9.49 RT	46.47
	STA. 433+74.75 TO 434+27.04	12.61 RT	64.20
	<b>TOTAL:</b>		<b>499.00 SO YD</b>

CAL MO	LOCATION	QUANTITY
67000400	ENGINEER'S FIELD OFFICE, TYPE A	
	US BUS 20	
	STA. 428+85.25 TO 434+27.04	10.00
	<b>TOTAL:</b>	<b>10.00 CAL MO</b>

FOOT	LOCATION	OFFSET	OFFSET	LOCATION	STAGE	COLOR	QUANTITY
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"						
	US BUS 20						
	STA. 411+11.52	26.80	TO 411+60.00	28.00	RT	1	SOLID WHITE 48.49
	STA. 411+60.00	28.00	TO 425+66.00	28.00	RT	1	SOLID WHITE 1406.00
	STA. 426+80.00	28.00	TO 434+50.00	28.00	RT	1	SOLID WHITE 770.00
	STA. 434+50.00	28.00	TO 433+30.00	26.00	RT	1	SOLID WHITE 120.02
	STA. 405+00.00	2.00	TO 411+60.00	18.00	RT	1	SOLID YELLOW 660.19
	STA. 411+60.00	18.00	TO 425+00.00	18.00	RT	1	SOLID YELLOW 1340.00
	STA. 425+00.00	18.00	TO 425+66.00	18.00	RT	1	SOLID YELLOW 66.00
	STA. 426+80.00	18.00	TO 427+00.00	18.00	RT	1	SOLID YELLOW 20.00
	STA. 427+00.00	18.00	TO 434+50.00	18.00	RT	1	SOLID YELLOW 750.00
	STA. 434+50.00	18.00	TO 443+30.00	16.00	RT	1	SOLID YELLOW 880.00
	STA. 418+50.00	2.00	TO 425+00.00	17.08	LT/RT	1	SOLID YELLOW 650.28
	STA. 425+00.00	17.08	TO 425+66.00	17.08	RT	1	SOLID YELLOW 66.00
	STA. 426+80.00	17.08	TO 434+50.00	17.08	RT	1	SOLID YELLOW 770.00
	STA. 434+50.00	17.08	TO 443+30.00	2.00	RT/LT	1	SOLID YELLOW 880.21
	STA. 443+30.00	2.00	TO 449+90.00	2.00	LT	1	SOLID YELLOW 660.00
	STA. 418+50.00	12.00	TO 425+00.00	7.08	LT/RT	1	SOLID WHITE 650.28
	STA. 425+00.00	7.08	TO 434+50.00	7.08	RT	1	SOLID WHITE 950.00
	STA. 434+50.00	7.08	TO 443+30.00	12.00	RT/LT	1	SOLID WHITE 880.21
	STA. 443+30.00	12.00	TO 449+90.00	12.00	LT	1	SOLID WHITE 660.00
	STA. 449+90.00	12.00	TO 453+20.00	20.00	LT	1	SOLID WHITE 330.10
	STA. 453+20.00	20.00	TO 456+50.00	26.00	LT	1	SOLID WHITE 330.05
	STA. 406+30.00	27.00	TO 412+90.00	12.50	RT	2	SOLID WHITE 660.16
	STA. 412+90.00	12.50	TO 419+50.00	12.50	RT	2	SOLID WHITE 660.00
	STA. 419+50.00	12.50	TO 425+50.00	7.42	RT/LT	2	SOLID WHITE 600.33
	STA. 427+44.00	7.42	TO 428+50.00	7.42	LT	2	SOLID WHITE 106.00
	STA. 428+50.00	7.42	TO 435+25.00	7.42	LT	2	SOLID WHITE 675.00
	STA. 435+25.00	7.42	TO 451+75.00	13.00	LT/RT	2	SOLID WHITE 1650.13
	STA. 451+75.00	13.00	TO 455+05.00	14.00	LT/RT	2	SOLID WHITE 330.00
	STA. 412+90.00	2.00	TO 419+50.00	2.00	RT	2	SOLID YELLOW 660.00
	STA. 419+50.00	2.00	TO 425+50.00	18.88	RT/LT	2	SOLID YELLOW 600.36
	STA. 425+50.00	18.88	TO 435+25.00	18.88	LT	2	SOLID YELLOW 975.00
	STA. 435+25.00	18.88	TO 451+75.00	2.00	LT/RT	2	SOLID YELLOW 1650.13
	STA. 451+75.00	2.00	TO 455+05.00	2.00	RT	2	SOLID YELLOW 330.00
	STA. 412+90.00	12.90	TO 425+50.00	18.90	LT	2	SOLID YELLOW 1260.01
	STA. 425+50.00	18.90	TO 428+50.00	18.90	LT	2	SOLID YELLOW 300.00
	STA. 428+50.00	18.90	TO 435+25.00	18.90	LT	2	SOLID YELLOW 675.00
	STA. 435+25.00	18.90	TO 448+45.00	15.50	LT	2	SOLID YELLOW 1320.00
	STA. 448+45.00	15.50	TO 455+05.00	2.00	LT	2	SOLID YELLOW 660.14
	STA. 415+00.00	26.00	TO 425+50.00	29.42	LT	2	SOLID WHITE 1050.01
	STA. 425+50.00	29.42	TO 435+25.00	29.42	LT	2	SOLID WHITE 975.00
	STA. 435+25.00	29.42	TO 448+45.00	26.00	LT	2	SOLID WHITE 1320.00
	<b>TOTAL:</b>						<b>29346.00 FOOT</b>

FOOT	LOCATION	QUANTITY
63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	
	US BUS 20	
	STA. 428+85.25 TO 429+35.19	LT 50.00
	STA. 429+46.51 TO 430+21.48	RT 75.00
	STA. 432+89.81 TO 433+77.01	LT 87.50
	STA. 433+77.12 TO 434+27.04	RT 50.00
	<b>TOTAL:</b>	<b>262.50 FOOT</b>

L SUM	LOCATION	QUANTITY
67100100	MOBILIZATION	
	US BUS 20	
	STA. 428+85.25 TO 434+27.04	1
	<b>TOTAL:</b>	<b>1.00 LSUM</b>

EACH	LOCATION	QUANTITY
70100310	TRAFFIC CONTROL AND PROTECTION STANDARD 70142I	
	US BUS 20	
	STA. 406+50.00 TO 456+50.00	1
	<b>TOTAL:</b>	<b>1.00 EACH</b>

EACH	LOCATION	LENGTH	QUANTITY
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		
	US BUS 20		
	STA. 429+34.90	32.83 429+78.65	LT 43.75 1.00
	STA. 430+26.45	32.83 430+70.20	RT 43.75 1.00
	STA. 432+46.06	32.83 432+89.81	LT 43.75 1.00
	STA. 433+32.61	32.83 433+76.36	RT 43.75 1.00
	<b>TOTAL:</b>		<b>4.00 EACH</b>

EACH	LOCATION	QUANTITY
70100400	TRAFFIC CONTROL AND PROTECTION STANDARD 70143I	
	US BUS 20	
	STA. 406+50.00 TO 456+50.00	1
	<b>TOTAL:</b>	<b>1.00 EACH</b>

FILE NAME = s:\p1\6380--6395\6346\025\micro\cadd sheets\0264E76-sh1-Schedule.dgn



1170 SOUTH HOUBOLT ROAD JOLIET, ILLINOIS 60431 (815) 744-4200	USER NAME = brianf	DESIGNED - EMD	REVISED -
	PLOT SCALE = 40.0000' / IN.	DRAWN - BJB	REVISED -
	PLOT DATE = 8/6/2012	CHECKED - VLF	REVISED -
		DATE - 02/29/12	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: AS SHOWN	SHEET	OF	SHEETS	STA.	TO STA.
-----------------	-------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5	(19VB-1D)	STEPHENSON	73	14
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64E76	