

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION	US BUS 20	OFFSET	LENGTH	QUANTITY
		STA. 429+50.00 TO 430+39.14	2.00	89.14	4.00
		STA. 429+50.00 TO 430+33.82	2.00	83.82	4.00
		STA. 429+50.00 TO 430+55.11	14.00	105.11	3.00
		STA. 432+95.45 TO 433+50.00	14.00	54.55	2.00
		STA. 429+50.00 TO 430+17.84	14.00	67.84	2.00
		STA. 432+56.18 TO 433+50.00	14.00	93.82	3.00
TOTAL:					18.00 EACH

X7810400 TEMPORARY RAISED PAVEMENT MARKER

EACH	LOCATION	US BUS 20	SPACING	NUMBER PER SIDE	STAGE	QUANTITY
		STA. 418+50.00 TO 425+00.00	20.00	2.00	1	65.00
		STA. 434+50.00 TO 449+90.00	20.00	2.00	1	154.00
		STA. 419+50.00 TO 425+00.00	20.00	2.00	2	55.00
		STA. 435+25.00 TO 451+75.00	20.00	2.00	2	165.00
TOTAL:						439.00 EACH

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	US BUS 20	LENGTH (FT)	QUANTITY
		STA. 428+85.25 TO 429+35.19	49.94	2.00
		STA. 429+46.51 TO 430+21.48	74.97	2.00
		STA. 432+89.81 TO 433+77.01	87.20	2.00
		STA. 433+77.12 TO 434+27.04	49.92	2.00
TOTAL:				8.00 EACH

Z0004552 APPROACH SLAB REMOVAL

SO YD	LOCATION	US BUS 20	QUANTITY
		STA. 430+06.48 TO 430+36.48	220.35
		STA. 432+74.82 TO 433+04.82	218.95
TOTAL:			440.00 SO YD

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION	US BUS 20	LT/RT	LENGTH	QUANTITY
		STA. 429+78.34 TO 432+46.67	LT	268.33	5.00
		STA. 430+64.62 TO 433+32.96	RT	268.34	5.00
TOTAL:					10.00 EACH

Z0024476 FLEXIBLE DELINEATOR MAINTENANCE

EACH	LOCATION	US BUS 20	QUANTITY
		STA. 406+50.00 TO 456+50.00	20.00
TOTAL:			20.00 EACH

78300100 PAVEMENT MARKING REMOVAL

SO FT	LOCATION	US BUS 20	OFFSET	OFFSET	COLOR	QUANTITY
		STA. 411+11.52	26.80	425+66.00	25.83 RT	SOLID WHITE 484.83
		STA. 426+80.00	26.04	443+30.00	25.79 RT	SOLID WHITE 550.00
		STA. 405+00.00	14.00	410+22.83	14.67 RT	WHITE DASHED 65.35
		STA. 423+89.87	13.86	437+10.54	13.23 RT	WHITE DASHED 165.08
		STA. 450+28.85	14.00	456+50.00	14.00 RT	WHITE DASHED 77.64
		STA. 419+74.79	1.71	423+80.86	3.59 RT	SOLID YELLOW 270.72
		STA. 418+50.00	2.68	421+95.56	1.85 LT	SOLID YELLOW 230.37
		STA. 437+17.19	3.11	442+25.32	1.02 RT	SOLID YELLOW 338.76
		STA. 439+19.87	0.98	449+89.89	2.00 LT	SOLID YELLOW 713.35
		STA. 415+00.00	25.83	428+75.02	25.50 LT	SOLID WHITE 458.34
		STA. 433+77.01	25.60	448+45.00	25.50 LT	SOLID WHITE 489.33
		STA. 423+91.77	14.01	438+69.05	12.96 LT	WHITE DASHED 184.66
		STA. 448+75.74	13.00	455+05.00	13.45 LT	WHITE DASHED 78.66
		STA. 412+90.10	2.00	422+59.08	1.63 RT	SOLID YELLOW 645.99
		STA. 420+54.13	1.78	424+13.40	3.82 LT	SOLID YELLOW 239.52
		STA. 425+26.16	1.63	425+86.82	2.35 RT	SOLID YELLOW 40.44
		STA. 425+01.27	3.77	425+86.90	2.66 LT	SOLID YELLOW 57.09
		STA. 441+55.30	1.26	455+05.00	1.99 RT	SOLID YELLOW 899.80
		STA. 438+32.84	2.92	451+67.59	-1.62 LT	SOLID YELLOW 889.84
		STA. 418+50.00	0.00	423+80.86	LT/RT	YELLOW MEDIAN DIAGONAL 28.31
		STA. 437+17.19	0.00	449+89.89	LT/RT	YELLOW MEDIAN DIAGONAL 67.88
		STA. 412+90.10	0.00	424+13.40	LT/RT	YELLOW MEDIAN DIAGONAL 59.91
		STA. 425+01.27	0.00	425+86.90	LT/RT	YELLOW MEDIAN DIAGONAL 4.57
		STA. 438+32.84	0.00	455+05.00	LT/RT	YELLOW MEDIAN DIAGONAL 89.18
TOTAL:						7130.00

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	US BUS 20	QUANTITY
		STA. 425+97.88	1
		STA. 436+00.25	1
TOTAL:			2.00 EACH

Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	US BUS 20	QUANTITY
		STA. 427+31.29	1
		STA. 437+36.44	1
TOTAL:			2.00 EACH

FILE NAME = s:\p1\6380--6395\6346\025\micro\cadd sheets\0264E76-sh1-Schedule.dgn



USER NAME = brianf	DESIGNED - EMD	REVISED -
PLOT SCALE = 40.0000' / IN.	DRAWN - BJF	REVISED -
PLOT DATE = 8/6/2012	CHECKED - VLF	REVISED -
	DATE - 02/29/12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: AS SHOWN	SHEET	OF	SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5	(19VB-1)D	STEPHENSON	73	16
CONTRACT NO. 64E76				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				