

DATE	
BY	
SURVEYED	
TEMPERATURE	
WIND	
MOISTURE	
AREAS CHECKED	
FINAL SURVEY	
NOTE BOOK	
NO.	

DATE	
BY	
SURVEYED	
TEMPERATURE	
WIND	
MOISTURE	
AREAS CHECKED	
ORIGINAL SURVEY	
NOTE BOOK	
NO.	

SUMMARY OF QUANTITIES			CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	URBAN	0014 BRIDGE REPAIR 100% STATE		
			TOTAL QUANTITY			
78100300	REPLACEMENT REFLECTOR	EACH	26	26		
78200520	BARRIER WALL MARKERS, TYPE B	EACH	44	44		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3388	3388		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6		
Z0012754	STRUCTURAL REPAIR OF CONCRETE EQUAL TO OR LESS THAN 5 INCHES	SQ FT	621	621		
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	2.8	2.8		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	4.3	4.3		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	7.1	7.1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2		
Z0053750	RETROFIT CONCRETE PARAPET	FOOT	1149	1149		
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	1	1		
X5810015	BRIDGE DECK CONCRETE SEALER	SQ YD	31,482	31,482		
X0323818	CLEANING AND PAINTING EXPOSED REBAR	SQ FT	510	510		
X0024967	CONCRETE METH ACRYLATE SEALER	SQ YD	3498	3498		
JS701010	MAINTENANCE OF TRAFFIC	L SUM	1	1		

* SPECIALTY ITEM

FILE NAME: D264H73-ht-50003.dgn
 PLOT DATE: 9/21/2012
 PLOT SCALE: 100,0000 ' / IN.



CHRISTIAN-ROGE & ASSOCIATES, INC.
 ENGINEERS-PLANNERS-SURVEYORS
 211 WEST WACKER DRIVE
 CHICAGO, ILLINOIS 60606
 PHONE: (312)372-2023 FAX: (312)372-5274

DESIGNED - G.F.L./K.R.K.
 DRAWN - K.R.K.
 CHECKED - E.J.M.
 DATE - AUGUST 2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 I-39 OVER I-88

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	D2 DECK REPAIR 2013-1	OGLE	32	5
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 64H73	

Rev.