

SCHEDULE OF QUANTITIES

HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 40603310

			SOYD	INCHES	TONS
Stage 1					
NB	1401+40.00	1402+35.00	varies	146.7	2
SB	1412+70.00	1417+70.00	varies	222.2	2
Stage 2					
SB	1402+30.00	1407+61.20	6	354.1	2
SB	1410+38.80	1414+70.00	6	287.5	2
NB	1396+40.00	1407+34.00	6	729.3	2
NB	1410+14.20	1414+70.00	6	303.9	2
TOTAL					228.9

HOT-MIX ASPHALT SURFACE REMOVAL, 2" 44000157

			SOYD		
Stage 1					
NB	1401+40.00	1402+35.00	varies	146.7	
SB	1412+70.00	1417+70.00	varies	222.2	
Stage 2					
SB	1402+30.00	1407+61.20	6	354.1	
SB	1410+38.80	1414+70.00	6	287.5	
NB	1396+40.00	1407+34.00	6	729.3	
NB	1410+14.20	1414+70.00	6	303.9	
TOTAL					2043.7

SHOULDER RUMBLE STRIPS, 16 INCH 64200116

			FOOT	
Stage 1				
NB	1396+40.00	1402+75.00	635.0	
SB	1412+70.00	1414+70.00	200.0	
Stage 2				
SB	1402+30.00	1407+61.20	531.2	
SB	1410+38.80	1414+70.00	431.2	
NB	1401+40.00	1407+34.00	594.0	
NB	1410+14.20	1414+70.00	455.8	
TOTAL				2847.2

SHORT TERM PAVEMENT MARKING 70300100

				FOOT	SQ FT
NORTHBOUND					
4" YELLOW	1396+40.00	1414+70.00	1,830		610.0
4" WHITE	1401+00.00	1413+90.00	1,290		430.0
6" SKIP DASH	1386+90.00	1415+20.00	707.5		235.8
6" SKIP DASH	1406+40.00	1412+70.00	157.5		52.5
8" WHITE	1401+45.00	1406+30.00	970		323.3
8" WHITE	1412+75.00	1415+20.00	370		123.3
SOUTHBOUND					
4" YELLOW	1402+30.00	1414+70.00	1,240		413.3
4" WHITE	1404+00.00	1413+00.00	900		300.0
6" SKIP DASH	1402+80.00	1429+20.00	660.0		220.0
6" SKIP DASH	1405+00.00	1411+40.00	160.0		53.3
8" WHITE	1401+80.00	1405+10.00	470		155.7
8" WHITE	1411+45.00	1413+70.00	450		150.0
TOTAL					3068.2

WORK ZONE PAVEMENT MARKING REMOVAL 70300100

		70300220		
TEMPORARY PAVEMENT MARKING - LINE 4"				
STAGE I				
		YELLOW	WHITE	
SOUTHBOUND				
		FOOT	FOOT	SQ FT
	1401+95.00	1429+70.00	2,725	908.3
	1401+95.00	1404+75.00		93.3
	1403+69.00	1404+75.00		35.3
	1412+70.00	1414+70.00		66.7
	1412+70.00	1413+70.00		33.3
NORTH BOUND				
	1386+90.00	1416+05.00	2,915	971.7
	1401+40.00	1407+00.00		186.7
	1401+00.00	1407+00.00		200.0
(CHEVRONS)	1401+53.00	1404+85.00		39.0
	1401+00.00	1407+00.00		200.0
	1413+40.00	1415+05.00		55.0
	1413+40.00	1414+22.00		28.0
STAGE II				
SOUTHBOUND				
	1401+80.00	1404+40.00		86.7
	1402+30.00	1414+70.00	1,240	413.3
	1403+78.00	1404+40.00		25.0
	1404+00.00	1429+20.00		840.0
NORTH BOUND				
	1386+90.00	1402+50.00	1,560	520.0
	1396+40.00	1414+70.00	1,830	610.0
	1401+50.00	1402+50.00		33.3
	1401+50.00	1413+80.00		411.7
	1413+10.00	1414+21.00		37.0
	1413+10.00	1415+70.00		70.0
STAGE II (AT EXIT RAMP TO SB I-39)				
	4157+00.00	4163+00.00		200.0
TOTAL				6064.4
TOTAL				18,193

THERMOPLASTIC PAVEMENT MARKING - LINE 4" 78000200

		FOOT		
NORTHBOUND				
YELLOW	1396+40.00	1414+70.00	1,830	
YELLOW	1401+10.00	1401+45.00	35	
WHITE	1401+10.00	1413+90.00	1,280	
SOUTHBOUND				
YELLOW	1402+30.00	1414+70.00	1,240	
WHITE	1403+80.00	1413+70.00	990	
TOTAL				5375

THERMOPLASTIC PAVEMENT MARKING - LINE 8" 78000500

		FOOT		
NORTHBOUND				
WHITE	1401+45.00	1406+30.00	485	
WHITE	1401+45.00	1406+30.00	485	
WHITE	1412+75.00	1415+20.00	245	
WHITE	1412+75.00	1414+00.00	125	
SOUTHBOUND				
WHITE	1401+80.00	1405+10.00	330	
WHITE	1403+75.00	1405+10.00	140	
WHITE	1411+45.00	1413+70.00	225	
WHITE	1411+45.00	1413+70.00	225	
WHITE	1413+70.00	1414+20.00	50	
TOTAL				2310

THERMOPLASTIC PAVEMENT MARKING - LINE 5" 78000400

		FOOT		
NORTHBOUND				
SKIP DASH	1386+90.00	1415+20.00	707.5	
SKIP DASH	1406+30.00	1412+75.00	161.3	
SOUTHBOUND				
SKIP DASH	1402+80.00	1429+20.00	660.0	
SKIP DASH	1405+10.00	1411+45.00	158.8	
TOTAL				1687.6

REPLACEMENT REFLECTOR 78100300

		EACH		
NORTHBOUND				
SKIP-DASH	1386+90.00	1396+90.00	13	
SOUTHBOUND				
SKIP-DASH	1419+20.00	1429+20.00	13	
TOTAL				26

THERMOPLASTIC PAVEMENT MARKING - LINE 12" 78000600

		FOOT		
NORTHBOUND				
WHITE	1401+45.00	1406+30.00	62	
WHITE	1412+75.00	1415+20.00	80	
SOUTHBOUND				
WHITE	1401+80.00	1405+10.00	78	
WHITE	1411+45.00	1413+70.00	44	
TOTAL				264

TEMPORARY CONCRETE BARRIER 70400100

		FOOT		
STAGE I				
	1404+98.75	1411+34.68	625	
	1406+45.63	1413+00.54	650	
TOTAL				1275

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) 78100105

		LANES		EACH
NB				
	1407+48.05	1410+26.25	1	3
SB				
	1407+48.05	1410+26.25	1	3
TOTAL				6

RELOCATE TEMPORARY CONCRETE BARRIER 70400200

		FOOT		
STAGE 2				
	1405+49.44	1411+34.31	575	
	1406+45.29	1413+00.41	650	
TOTAL				1225

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL 78300200

		LANES		EACH
NB				
	1407+48.05	1410+26.25	1	3
SB				
	1407+48.05	1410+26.25	1	3
TOTAL				6

BARRIER WALL MARKERS, TYPE B 78200520

		25' SPACING		EACH
NORTH BOUND				
	1407+48.00	1410+27.00	/25	11
	1407+48.00	1410+27.00		11
SOUTH BOUND				
	1407+48.00	1410+27.00		11
	1407+48.00	1410+27.00		11
TOTAL				44

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 20030250

STAGE I				
	1412+99.60	SB		1
	1404+75.40	NB		1
TOTAL				2

IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 20030350

STAGE II				
	1412+99.60	SB		1
	1404+75.40	NB		1
TOTAL				2

PAVEMENT MARKING REMOVAL 78300100

		FOOT		SQ FT
STAGE I				
NORTHBOUND				
4" YELLOW	1401+00.00	1401+50.00	50	16.7
4" WHITE	1401+00.00	1407+00.00	600	200.0
6" SKIP DASH	1386+90.00	1407+30.00	510	255.0
6" SKIP DASH	1406+30.00	1412+80.00	163	81.3
6" SKIP DASH	1410+10.00	1415+05.00	124	61.9
8" WHITE	1401+40.00	1407+30.00	590	393.3
8" WHITE	1401+40.00	1407+30.00	590	393.3
8" WHITE	1412+80.00	1415+05.00	290	193.3
SOUTHBOUND				
4" WHITE	1413+70.00	1414+70.00	100	33.3
6" SKIP DASH	1402+95.00	1407+60.00	116	58.1
6" SKIP DASH	1405+20.00	1411+40.00	155	77.5
6" SKIP DASH	1409+90.00	1429+20.00	483	241.3
8" WHITE	1402+95.00	1405+10.00	250	166.7
8" WHITE	1411+40.00	1413+70.00	230	153.3
8" WHITE	1411+40.00	1413+70.00	230	153.3
STAGE II				
NORTHBOUND				
4" YELLOW	1396+40.00	1409+60.00	1,320	440.0
4" YELLOW	1410+10.00	1414+70.00	460	153.3
SOUTHBOUND				
4" YELLOW	1402+30.00	1407+30.00	500	166.7
4" YELLOW	1410+20.00	1414+70.00	450	150.0
TOTAL				3388.3

DATE: \_\_\_\_\_  
BY: \_\_\_\_\_  
CHECKED BY: \_\_\_\_\_  
SCALE: 1" = 40' (VERTICAL)  
SCALE: 1" = 100' (HORIZONTAL)  
NOTE: REFER TO DRAWING SHEET FOR MARKING LAYOUT

DATE: \_\_\_\_\_  
BY: \_\_\_\_\_  
CHECKED BY: \_\_\_\_\_  
SCALE: 1" = 40' (VERTICAL)  
SCALE: 1" = 100' (HORIZONTAL)  
NOTE: REFER TO DRAWING SHEET FOR MARKING LAYOUT