


SUMMARY OF QUANTITIES				LOIE	LICE				LOIE	90% FEDERAL LICE	10% STATE	LOIE				100% VILLAGE OF MORTON	
				ROADWAY FAI 74 / FAI 155	I-155 OVER I-74 (RAMPS G & H)	I-74 OVER ABANDONED RAILROAD DEMOLITION	I-74 OVER JEFFERSON ST	I-74 OVER US 150 (JACKSON ST)	I-74 / I-155	MORTON AVE. OVER I-74	TRAFFIC SIGNALS	LIGHTING	SIGNING	LANDSCAPING	INTELLIGENT TRANSPORTATION SYSTEM	PINECREST DR PLANS	EMERGENCY VEHICLE PRE-EMPTION
				I-74 / I-155	SN 090-0165 (SB) SN 090-0166 (NB)	SN 090-0014 (WB) SN 090-0015 (EB)	SN 090-0167	SN 090-0169	OVERHEAD SIGN STRUCTURES	SN 090-0141							
CODE	ITEM	UNIT	TOTAL QUANTITY	0003	0008	0044	0010	0010	0040	0014	0021	0021	0021	0031	0021	0014	0021
* 81702180	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 3/0	FOOT	855									855					
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	123									123					
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	138									138					
* 82107200	UNDERPASS LUMINAIRE, 100 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	8									8					
* 82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	3									3					
83060345	LIGHT POLE, GALVANIZED STEEL, 40 FT. M.H., 12 FT. MAST ARM, TWIN	EACH	11									11					
83060350	LIGHT POLE, GALVANIZED STEEL, 40 FT. M.H., 15 FT. MAST ARM	EACH	101									101					
83060543	LIGHT POLE, GALVANIZED STEEL, 50 FT. M.H., 12 FT. MAST ARM, TWIN	EACH	48									48					
83060550	LIGHT POLE, GALVANIZED STEEL, 50 FT. M.H., 15 FT. MAST ARM	EACH	39									39					
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	867									867					
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	138									138					
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	38									38					
84200804	REMOVAL OF POLE FOUNDATION	EACH	38									38					
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2									2					

\* SPECIALTY ITEM

FILE NAME *	DESIGNED - EJA	REVISED -	 engineers - scientists - planners	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES SCALE: NTS SHEET NO. 23 OF 34 SHEETS STA. TO STA.				F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...General\10468620-shv-S00_23.dgn	DRAWN - YMB	REVISED -										90-114R\114HB-4,14,14HVB\BRT	TAZEWELL	2433	30	
USER NAME : jeambillo	CHECKED - JNR	REVISED -		CONTRACT NO. 68620				ILLINOIS FED. AID PROJECT								
PLOT DATE : 7/30/2012	DATE - JULY 20, 2012	REVISED -														