

SUMMARY OF QUANTITIES				LO1E	LICE				LO1E	90% FEDERAL LICE	10% STATE	LO1E				100% VILLAGE OF MORTON	
CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	I-155 OVER	I-74 OVER	I-74 OVER	I-74 OVER	I-74 / I-155	MORTON AVE.	TRAFFIC SIGNALS	LIGHTING	SIGNING	LANDSCAPING	INTELLIGENT TRANSPORTATION SYSTEM	PINECREST DR PLANS	EMERGENCY VEHICLE PRE-EMPTION
				FAI 74 / FAI 155	I-74 (RAMPS G & H)	ABANDONED RAILROAD DEMOLITION	JEFFERSON ST	US 150 (JACKSON ST)	OVER I-74	OVER I-74							
				0003	0008	0044	0010	0010	0040	0014							
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2									2					
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2									2					
86300300	CONTROLLER CABINET TYPE III	EACH	1	1													
* 87100020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	5,342												5,342		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,566								2,566						
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	893								893						
* 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	2,627								2,627						
* 87301732	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 20 3C	FOOT	913														913
87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	5								5						
87700400	STEEL MAST ARM ASSEMBLY AND POLE, 60 FT.	EACH	1								1						
87702218	STEEL MAST ARM ASSEMB. AND POLE WITH DUAL MAST ARMS, 20 FT. AND 36 FT.	EACH	1								1						
87702960	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 46 FT.	EACH	1								1						
87704519	STEEL COMB. MAST ARM ASMBLY & POLE WITH DUAL MAST ARMS, 48 FT. & 36 FT.	EACH	1								1						
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	15								15						

* SPECIALTY ITEMS

FILE NAME -	DESIGNED - EJA	REVISED -
...General\0468620-sht-500_24.dgn	DRAWN - TMB	REVISED -
USER NAME - preambillo	CHECKED - JNR	REVISED -
PLOT DATE - 7/30/2012	DATE - JULY 20, 2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. 24 OF 34 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	BO-114R(14)B-4,14,14HVBIBR	TAZEWELL	2433	31
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68620	