

LOCATION			AGGREGATE SUBGRADE IMPROVEMENT 8"	AGGREGATE SUBGRADE IMPROVEMENT 12"	STABILIZED SUBBASE HOT-MIX ASPHALT, 4"	AGGREGATE SHOULDERS, TYPE B 6"	PORTLAND CEMENT CONCRETE SHOULDERS 11"	PIPE UNDERDRAINS 4"	TEMPORARY PAVEMENT REMOVAL	AGGREGATE SHOULDER REMOVAL	WHITEWASHING FOR CONCRETE PAVEMENT	TEMPORARY PAVEMENT	TEMPORARY RAMP	GLARE SCREEN (NEW LOCATION)	GLARE SCREEN TO REMAIN	GLARE SCREEN ON-SITE	TEMPORARY CONCRETE BARRIER (NEW LOCATION)	TEMPORARY CONCRETE BARRIER TO REMAIN	TEMPORARY CONCRETE BARRIER ON-SITE
ROAD	STATION FROM	STATION TO	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	SQ YD	CU YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
I-474	-	456+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	36362.5
I-74	456+00.00	471+00.00	0	969	969	34	927	805	0	0	969	753	0	0	0	0	1675.0	0.0	
I-74	471+00.00	486+00.00	0	0	0	0	0	0	0	0	0	1352	0	0	0	0	3000.0	0.0	TEMPORARY CONCRETE BARRIER FROM PREVIOUS STAGE
I-74	486+00.00	501+00.00	0	0	0	0	0	0	0	0	0	1667	0	0	0	0	3000.0	0.0	
I-74	501+00.00	516+00.00	0	0	0	0	0	0	0	0	0	3448	806	0	0	0	3000.0	0.0	
I-74	516+00.00	531+00.00	0	0	0	0	0	0	0	0	0	6579	0	0	0	0	2625.0	0.0	
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	
I-74	531+00.00	546+00.00	0	0	0	9	0	0	0	0	0	5723	0	0	0	0	2500.0	0.0	
I-74	546+00.00	561+00.00	0	0	0	0	0	0	0	0	0	4551	500	0	0	0	2762.5	0.0	
I-74	561+00.00	576+00.00	0	0	0	0	0	0	0	0	0	380	1526	0	0	0	2562.5	0.0	FOOT
I-74	576+00.00	591+00.00	0	85	85	94	85	191	0	1	85	4711	149	0	0	0	4012.5	0.0	775.0
I-74	591+00.00	606+00.00	0	311	311	190	311	700	0	5	311	4337	0	0	0	0	2950.0	0.0	
I-74	606+00.00	621+00.00	0	876	876	166	813	1137	0	0	876	337	0	0	0	0	1300.0	0.0	RELOCATE TEMPORARY CONCRETE BARRIER
I-74	621+00.00	636+00.00	0	66	66	11	61	100	0	0	66	0	0	0	0	0	125.0	0.0	
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	
I-155	00+00.00	09+00.00	0	0	0	237	0	0	0	0	0	2504	0	0	0	0	2237.5	0.0	
I-155	09+00.00	23+00.00	0	354	354	323	336	320	0	0	354	2641	0	0	0	0	2900.0	0.0	
I-155	23+00.00	37+50.00	0	351	351	42	330	374	0	0	351	0	0	0	0	0	487.5	0.0	FOOT
I-155	37+50.00	51+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	775.0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	
Morton Ave.	16+00.00	28+25.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	TEMPORARY CONCRETE BARRIER
Morton Ave.	28+25.00	36+50.00	0	0	0	0	0	0	0	0	0	33	0	0	0	0	462.5	0.0	
Morton Ave.	36+50.00	44+75.00	516	0	0	10	0	0	6	0	0	516	0	0	0	0	762.5	0.0	
Morton Ave.	44+75.00	58+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0.0	0.0	
TOTALS			516	3012	3012	1116	2863	3628	6	6	3012	36512	6000	0	0	0	36362.5	0.0	35587.5

LOCATION			PAVEMENT MARKING TAPE, TY III LETTERS & SYMBOLS	PAVEMENT MARKING TAPE, TYPE III 4"	PAVEMENT MARKING TAPE, TYPE III 8"	PAVEMENT MARKING TAPE, TYPE III 12"	PAVEMENT MARKING TAPE, TYPE III 24"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING TYPE II LINE 4"	POLYUREA PAVEMENT MARKING TYPE II LINE 8"	POLYUREA PAVEMENT MARKING TYPE II LINE 12"
ROAD	STATION FROM	STATION TO	SQ FT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT
I-474	-	456+00.00	0	5141	0	0	0	433	0	0	0
I-74	456+00.00	471+00.00	0	4361	0	0	0	0	1564	0	0
I-74	471+00.00	486+00.00	0	600	0	0	0	0	6546	0	0
I-74	486+00.00	501+00.00	0	0	0	0	0	0	4875	0	0
I-74	501+00.00	516+00.00	0	0	0	0	0	0	5219	633	0
I-74	516+00.00	531+00.00	0	0	0	0	0	0	7354	1852	0
RAMP G/H	118+50.00	101+47.00	0	0	0	0	0	0	0	0	0
I-74	531+00.00	546+00.00	0	0	0	0	0	546	8032	230	0
I-74	546+00.00	561+00.00	0	0	0	0	0	500	7459	213	0
I-74	561+00.00	576+00.00	0	0	0	0	0	67	8356	0	0
I-74	576+00.00	591+00.00	0	288	0	0	0	1748	8667	759	0
I-74	591+00.00	606+00.00	0	3186	450	0	0	897	3945	400	0
I-74	606+00.00	621+00.00	0	2170	0	0	0	218	2182	105	0
I-74	621+00.00	636+00.00	0	991	0	0	0	500	0	0	0
I-74	636+00.00	640+00.00	0	0	0	0	0	0	0	0	0
I-155	00+00.00	09+00.00	0	0	0	0	0	0	6026	1378	0
I-155	09+00.00	23+00.00	0	682	0	0	0	35	5893	121	0
I-155	23+00.00	37+50.00	0	2838	579	0	0	521	0	0	0
I-155	37+50.00	51+00.00	0	0	0	0	0	408	0	0	0
I-155	51+00.00	66+00.00	0	0	0	0	0	0	0	0	0
Morton Ave.	16+00.00	28+25.00	18	2802	0	576	0	316	0	0	0
Morton Ave.	28+25.00	36+50.00	39	5175	227	348	65	996	0	0	0
Morton Ave.	36+50.00	44+75.00	0	3925	361	0	42	929	0	0	0
Morton Ave.	44+75.00	58+00.00	0	1790	426	0	0	270	0	0	0
TOTALS			56	33949	2043	924	107	8381	76117	5692	0

	SHORT TERM PAVEMENT MARKING	CHANGEABLE MESSAGE SIGN
	FOOT	CAL MO
TOTAL STAGE 1	5,943	20.75

ATTENUATOR LOCATION SCHEDULE				IMPACT ATTENUATORS WIDE NEW OR RELOCATED EACH	IMPACT ATTENUATORS WIDE TO REMAIN EACH	IMPACT ATTENUATORS NARROW NEW OR RELOCATED EACH	IMPACT ATTENUATORS NARROW TO REMAIN EACH
ROAD	STATION	OFFSET	TYPE				
I-74	459+50.81	34.85	WIDE	1	0	0	0
I-74	582+94.18	56.5	WIDE	1	0	0	0
I-74	605+25.29	-16.25	NARROW	0	0	1	0
I-155	12+45.23	24.68	NARROW	0	0	1	0
I-155	40+14.44	-29.63	WIDE	1	0	0	0

	TEST LEVEL 2 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 2 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDRCTVE), TEST LVL 2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDRCTVE, NARROW TEST LVL 2	IMPACT ATTENUATORS, RELOCATE (FULLY REDRCTVE, TEST LVL 2	IMPACT ATTENUATORS, RELOCATE (NON-REDRCTVE), TEST LVL 2
WIDE	0	0	0	0	-	-	0
NARROW	0	0	0	-	0	0	-

	TEST LEVEL 3 ATTENUATORS NEW OR RELOCATED	TEST LEVEL 3 ATTENUATORS TO REMAIN	ATTENUATORS FROM PREVIOUS STAGE	IMPACT ATTENUATORS TEMPORARY (NON-REDRCTVE), TEST LVL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDRCTVE, NARROW TEST LVL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDRCTVE, TEST LVL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDRCTVE), TEST LVL 3
WIDE	3	0	0	3	-	-	0
NARROW	2	0	0	-	2	0	-