

SIGN INDEX #	SIGN CODE	STA	OFFSET	DTL SHT #	ALIGNMENT	DIRECTION	EX OVRHD STR	EX STANDARD	EX SPECIAL	TEMP STD	TEMP SPCL	PROPOSED	DESCRIPTION	NEW STA.	NEW OFFSET	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE GROUND MOUNTED SUPPORT	REMOVE CONCRETE FOUNDATIONS MOUNT	TEMPORARY SIGN PANEL ASSEMBLY	TEMPORARY SIGN PANEL OVERLAY	CONSTRUCT PROPOSED SIGN (SEE SIGN PLAN)	
																EACH	EACH	EACH	EACH	SQ FT	SQ FT		
2T.01-R		-	-	262	I-74	EB						X	I-74 E ALL LANES, I-155 S RT LANE ONLY 1 MILE	415+91.00							175		
2T.01-L		-	-	262	I-74	EB						X	I-74 E ALL LANES, I-155 S RT LANE ONLY 1 MILE	415+91.00							175		
2T.03		-	-	262	I-74	EB						X	I-74 E ALL LANES, I-155 S RT LANE ONLY 1/2 MILE	442+31.05	-5.63						175		
2T.02-R		-	-	262	I-474	EB						X	I-74 E ALL LANES, I-155 S RT LANE ONLY 1 MILE	415+91.00							175		
2T.02-L		-	-	262	I-474	EB						X	I-74 E ALL LANES, I-155 S RT LANE ONLY 1 MILE	415+91.00							175		
2T.04		-	-	262	I-474	EB						X	I-74 E ALL LANES, I-155 S RT LANE ONLY 1/2 MILE	442+31.19	102.02						175		
3.01-2.2		-	-	264	I-74	EB						X	OVERLAY - "KEEP RIGHT"	460+42.00								21	
4.05	D10-6	481+21.46	68.17	-	I-74	EB		X					MILE MARKER 100			1.00							
PR4.05		-	-	-	I-74	EB						X	PROPOSED MILE MARKER (101)	PR	PR								X
4.07-2.2		-	-	264	I-74	EB						X	OVERLAY - "RIGHT LANE"	482+48.00								21	
6T.01		503+00.00	81.00	266	I-74	EB						X	I-74 AHEAD EXIT I-155 SOUTH LINCOLN EXIT 101	518+00.00	35.00						RELOCATE		
7.01	D9-I105	526+27.85	65.31	-	I-74	EB			X				EXIT 101 W/ ARROW	523+64.50	30.00						RELOCATE		
10.01	W4-1R	546+91.00	69.68	-	I-74	EB		X					MERGE								1.00		
12.09	D9-8	589+00.00	227.09	-	I-74	EB			X				BLUE FOOD SIGN				2		2				
PR18.06	R2-1	-	-	-	MORTON	SB						X	SPEED LIMIT 40	PR	PR								X
TOTALS																1	1	2	2	1050	43		

TEMPORARY SIGN SCHEDULE

FILE NAME = D468620-sh1-sign02-02.dgn	DESIGNED - HTL	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC STAGE 2A SIGN SCHEDULE	F.A.I. RTE. *	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
USER NAME = TERRA	DRAWN - KV	REVISED -				90-[14R;(14HB-4,14,14HVB)BR]	TAZEWELL	2433	98	
PLOT DATE = 7/18/2012	CHECKED - DA/LVA	REVISED -				CONTRACT NO. 68620				
	DATE - 7/20/2012	REVISED -				ILLINOIS FED. AID PROJECT				