

SIGN INDEX #	SIGN CODE	STA	OFFSET	DTL SHT #	ALIGNMENT	DIRECTION	EX OVRHD STR	EX STANDARD	EX SPECIAL	TEMP STD	TEMP SPCL	PROPOSED	DESCRIPTION	NEW STA.	NEW OFFSET	REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	REMOVE SIGN PANEL - TYPE 3	REMOVE CONCRETE FOUNDATIONS - OVERHEAD	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	TEMPORARY SIGN PANEL ASSEMBLY
																EACH	EACH	SQ FT	EACH	EACH	SQ FT
PR7.03		530+01.32	80.84	-	I-74	EB						X	BLUE LODGING SIGN	713+00.00	56.00						RELOCATE
7.01	D9-I105	523+94.50	70	-	I-74	EB			X				EXIT 101 W/ ARROW	709+00.00	55.21						RELOCATE
PR9.03		535+86.15	87.2	-	I-74	EB						X	PROPOSED MORTON EXIT 1 MILE	719+00.00	58.50						RELOCATE
9.09	W1-8	1201+57.49	-26.2	-	RAMP E	-			X				CHEVRON								REMOVE
9.11	W1-8	1202+55.61	-28	-	RAMP E	-			X				CHEVRON								REMOVE
9.13	W1-8	1203+50.75	-26.5	-	RAMP E	-			X				CHEVRON								REMOVE
PR9.15		543+14.84	67.82	-	I-74	EB						X	BLUE FOOD SIGN	725+50.00	58.50						RELOCATE
21.14-0.1		523+94.50	70	272	I-155	NB					X		OVERLAY "EXIT CLOSED"	17+68.00	OH						RELOCATE
21.14V-1	D1-I003a	11+57.00	OH	-	I-155	NB			X				I-74 WEST, PEORIA ARROW				REMOVE				
21.14V-2	D1-I003b	11+57.00	OH	-	I-155	NB			X				I-74 EAST, BLOOMINGTON ARROW				REMOVE				
21.02	W1-8	1200+58.77	-27	-	RAMP E	-			X				CHEVRON RIGHT								REMOVE
21.04	W1-8	9+91.00	-103	-	I-155	NB			X				CHEVRON RIGHT			1.00					
21.06	W1-8	10+86.00	-63.4	-	I-155	NB			X				CHEVRON RIGHT			1.00					
21.12	W13-3	13+19.00	-82	-	I-155	NB			X				40 MPH RAMP			1.00					
21T.16		-	-	273	I-155	NB					X		I-74 EAST, BLOOMINGTON ARROW	13+52.66	-41.83						105
22DH.02		28+00.00	-77	273	I-155	NB					X		DETOUR SIGN I-74 WEST, PEORIA W/ ARR	31+00.00	-8.50						RELOCATE
9.01	D10-6	534+13.00	59.86	-	I-74	EB			X				MILE MARKER	717+00.00	49.00	1.00					RELOCATE
13DH.01		591+60.00	72.5	270	I-74	EB					X		DETOUR SIGN I-74 WEST, PEORIA ONLY								REMOVE
21.14S	OVRHD STR	11+57.00		-			X						OVERHEAD SIGN STRUCTURE					2	1		
TOTALS																1	3	0	2	1	105

TEMPORARY SIGN SCHEDULE

FILE NAME =	DESIGNED - HTL	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC STAGE 6 SIGN SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D468620-sh1-sign03-06.dgn	DRAWN - KV	REVISED -				*	90-[14R;(14HB-4,14,14HVB)BR]	TAZEWELL	2433	122
USER NAME = TERRA	CHECKED - DA/LVA	REVISED -				CONTRACT NO. 68620				
PLOT DATE = 7/18/2012	DATE - 7/20/2012	REVISED -				SCALE:	SHEET NO. 46 OF 85 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	