



JEFFERSON STREET DETOUR PLAN
DETOUR LENGTH = 4200 FEET

NOTES

- 1) JEFFERSON STREET WILL BE CLOSED TO REPLACE EXISTING TUNNELS WITH NEW BRIDGES CARRYING I-74 ACROSS JEFFERSON STREET.
- 2) THE DURATION OF CLOSURE WILL BE DURING I-74 CONSTRUCTION STAGE 1-3 FOR MEDIAN, EB, AND WB, LANES RESPECTIVELY, OF THE EAST SEGMENT BETWEEN I-155 AND MORTON AVENUE.

LEGEND

- LOCAL ROAD
- DETOUR ROUTE
- ▨▨▨▨▨▨ ROADWAY CLOSURE
- TCP• SIGN INCLUDED IN TRAFFIC CONTROL & PROTECTION (SEE SIGN SCHEDULE)
- XX-X SIGN REFERENCE NUMBER (SEE SIGN SCHEDULE)

FILE NAME =	DESIGNED - DA	REVISED - 09/16/11
D468620-Detour Jefferson-st.dgn	DRAWN - KV	REVISED -
USER NAME = TERRA	CHECKED - HTL/LVA	REVISED -
PLOT DATE = 7/16/2012	DATE - 7/20/2012	REVISED -



STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

MAINTENANCE OF TRAFFIC
JEFFERSON ST DETOUR PLAN

SCALE: SHEET NO. 52 OF 52 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	90-[14R(14HB-4,14,14HB)BR]	TAZEWELL	2433	375
CONTRACT NO. 68620				
ILLINOIS FED. AID PROJECT				