

LEGEND


- | | |
|--|--|
| <ul style="list-style-type: none"> DRUMS WITH STEADY BURNING WARNING LIGHTS DIRECTION INDICATOR BARRICADE WITH STEADY BURN MONODIRECTIONAL LIGHT VERTICAL DELINEATOR PANELS BARRICADE, TYPE III FLASHING ARROW BOARD DIRECTION OF TRAFFIC FLOW IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE) IMPACT ATTENUATOR, TEMPORARY (NARROW, REDIRECTIVE) *TCP* SIGN INCLUDED IN TRAFFIC CONTROL & PROTECTION (SEE SIGN SCHEDULE) | <ul style="list-style-type: none"> TEMPORARY PAVEMENT CONSTRUCTION ON-GOING EARTHWORK FOR PROPOSED PAVEMENT PROPOSED PAVEMENT CONSTRUCTION TEMP PVMT REMOVAL (SEE REMOVAL PLAN FOR EX PVMT REMOVAL) REM TEMP AGGREGATE SHOULDERS AGGREGATE SHOULDERS, TYPE B 6" TEMPORARY CONCRETE BARRIER TEMPORARY CONCRETE BARRIER WITH 36" GLARE SCREEN SIGN REFERENCE NUMBER (SEE SIGN SCHEDULE) |
|--|--|

NOTE

1. RAMPS G & H COMPLETE. PROPOSED PAVEMENT MARKINGS AND SIGNS IN PLACE ON RAMP G & H. (SEE SIGN AND PAVEMENT MARKING PLAN)

PAVEMENT MARKING LEGEND

- | | | |
|---|---|--------------------------------|
| ① EXISTING PAVEMENT MARKING | 4SW 4" SOLID WHITE | 8SW 8" SOLID WHITE |
| ② PAVEMENT MARKING FROM PREVIOUS STAGE | 4SY 4" SOLID YELLOW | 12SW 12" SOLID WHITE |
| ③ PROPOSED PAVEMENT MARKING IN PLACE (SEE PROPOSED PAVEMENT MARKING PLAN) | 4SYY 4" SOLID DOUBLE YELLOW (11" C-C) | 12SY 12" SOLID YELLOW |
| T PAVEMENT MARKING TAPE, TYPE III | 4KW 4" SKIP-DASH WHITE (30' SKIP, 10' DASH) | 24SW 24" SOLID WHITE STOP BAR |
| P POLYUREA PAVEMENT MARKING TYPE II | 4DW 4" DOTTED WHITE (9' SKIP, 3' DASH) | LSW LETTERS AND SYMBOLS, WHITE |



FILE NAME =	DESIGNED - HTL	REVISED -		STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAINTENANCE OF TRAFFIC 2014 WINTER SHUTDOWN	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
D468620-sh1-staging07_174-12WS2.dgn	DRAWN - JPS	REVISED -				90-[14R(14HB-4,14,14HB)BR]	TAZEWELL	2433	1165	
USER NAME = TERRA	CHECKED - DA/LVA	REVISED -				CONTRACT NO. 68620				
PLOT DATE = 7/16/2012	DATE - 7/20/2012	REVISED -				ILLINOIS FED. AID PROJECT				