



**SCHEDULE OF QUANTITIES  
ITS PLAN SHEET 9**

UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	3750.0
CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	390.0
HEAVY-DUTY HANDHOLE	EACH	3.0
FIBER OPTIC CABLE 48 FIBERS, SINGLE MODE	EACH	1475.0

FILE NAME =	USER NAME = tblank	DESIGNED -	REVISED -
... \ITS (DDOT)\D468620-ITS-09.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**ITS FIBER PLANS  
I-74 TO MORTON AVE. INTERCHANGE**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	90-[14R(14HB-4,14,14HB)BR]	TAZEWELL	2433	1673
<b>CONTRACT NO. 68620</b>				
ILLINOIS FED. AID PROJECT				

SCALE: NONE    SHEET NO. 9 OF 50 SHEETS    STA.    TO STA.