


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	STRUCTURE
				F. A. P. 574 80% FEDERAL 20% STATE	S. N. 029-0072 80% FEDERAL 20% STATE
				CONSTRUCTION TYPE CODE	CONSTRUCTION TYPE CODE
				0004	0011
50300260	BRIDGE DECK GROOVING	SO YD	453		453
50300280	CONCRETE ENCASEMENT	CU YD	8.4		8.4
50300300	PROTECTIVE COAT	SO YD	576		576
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	71090		71090
50800515	BAR SPLICERS	EACH	414		414
50800530	MECHANICAL SPLICERS	EACH	66		66
51201400	FURNISHING STEEL PILES HP10X42	FOOT	879		879
51202305	DRIVING PILES	FOOT	879		879
51203400	TEST PILE STEEL HP10X42	EACH	2		2
51500100	NAME PLATES	EACH	1		1
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	150	150	
54215550	METAL END SECTIONS 15"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	40		40
* 63000001	STEEL PLATE GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	462.5	462.5	

*SPECIALTY ITEM

USER NAME * USER#	DESIGNED -	REVISED -	 Allen Henderson & Associates, Inc. Civil and Structural Engineers Springfield, IL 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLGT SCALE * SCALES	DRAWN -	REVISED -		SCALE: NONE	SHEET NO. 4 OF 7 SHEETS	STA.	TO STA.	574	12BR-1	FULTON	62	6
PLOT DATE * DATE*	CHECKED -	REVISED -						CONTRACT NO. 68732				
	DATE -	REVISED -						FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				