

PAVEMENT MARKING SCHEDULE

LOCATION	PAINT PAVEMENT MARKING - LINE 4"		TEMPORARY PAVEMENT MARKING - LINE 4"		SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL
	SOLID YELLOW	SOLID WHITE	SOLID YELLOW	SOLID WHITE			
	FOOT	FOOT	FOOT	FOOT			
STA. 398+50 TO STA. 405+91					149	50	
STA. 398+50 TO STA. 405+91 LT. EDGE		741		741		247	
STA. 398+50 TO STA. 405+91 CENTERLINE N.P.Z.	1482		1482			494	
STA. 398+50 TO STA. 405+91 RT. EDGE		741		741		247	
STAGE I							
STA. 396+60 TO STA. 397+20 LT.							20
STA. 396+60 TO STA. 399+60 CENTERLINE							200
STA. 396+60 TO STA. 407+26 RT.							356
STA. 404+20 TO STA. 407+26 CENTERLINE							204
STA. 406+66 TO STA. 407+26 LT.							20
SUB-TOTAL	1482	1482	1482	1482			
TOTAL	2964	2964	2964	2964	149	1038	800

SHOULDER SCHEDULE

LOCATION	AGGREGATE SHOULDERS, TYPE A 8"	HMA SHOULDERS, 1 1/2"	HMA SHOULDERS, 8"
	SQ. YD.	SQ. YD.	SQ. YD.
	STA. 398+50 TO STA. 401+52.70 LT.		100.9
STA. 401+52.70 TO STA. 401+88.20 LT.			
STA. 402+64.20 TO STA. 402+99.70 LT.			
STA. 402+99.70 TO STA. 405+91 LT.		97.1	97.1
STA. 398+50 TO STA. 401+52.70 RT.	101		
STA. 401+52.70 TO STA. 401+88.5 RT.			
STA. 402+64.20 TO STA. 402+99.70 RT.			
STA. 402+99.70 TO STA. 403+85.5 RT.	28		
STA. 404+60.5 TO STA. 405+91 RT.	43		
TOTAL	172	198	198

POLMERIZED BITUMINOUS MATERIALS (PRIME COAT) SCHEDULE

LOCATION	QUANTITY
	TON
	STA. 398+50 TO STA. 399+30 - SURFACE COURSE
STA. 399+30 TO STA. 401+58.20 - SURFACE COURSE	0.15
STA. 402+93.70 TO STA. 404+45 - SURFACE COURSE	0.10
STA. 404+45 TO STA. 405+91 - SURFACE COURSE	0.15
STA. 399+60 TO STA. 401+58.20 - BINDER COURSE LIFTS	0.59
STA. 402+93.70 TO STA. 404+20 - BINDER COURSE LIFTS	0.57
STA. 398+50 TO STA. 401+58.70 LT. TOP SHOULDER	0.03
STA. 402+93.70 TO STA. 405+91 LT. TOP SHOULDER	0.03
TOTAL	1.7

HMA SURFACE REMOVAL SCHEDULE

LOCATION	HMA SURFACE REMOVAL 1 1/2"	HMA SURFACE REMOVAL - BUTT JOINT
	SQ. YD.	SQ. YD.
	STA. 398+50 TO STA. 399+30	
STA. 404+45 TO STA. 405+00		158.9
STA. 405+00 TO STA. 405+91	263	
TOTAL	263	390

HMA PAVEMENT SCHEDULE

LOCATION	HMA BINDER COURSE, IL-19.0, N50	HMA SURFACE COURSE, MIX "D", N50
	TON	TON
	STA. 398+50 TO STA. 399+30	
STA. 399+30 TO STA. 399+60		12.8
STA. 399+60 TO STA. 401+52.70	434	46.8
STA. 402+99.70 TO STA. 404+20	238	29.2
STA. 404+20 TO STA. 404+45		10.7
STA. 404+45 TO STA. 405+91		35.5
TOTAL	672	155

PIPE CULVERT SCHEDULE

LOCATION	PIPE CULVERTS, CLASS D TYPE 1 15"	METAL END SECTIONS 15"
	FOOT	EACH
	STA. 403+00, 29.3' RT. TO STA. 404+50, 28.9' RT.	150
TOTAL	150	2

GUARDRAIL AGGREGATE EROSION CONTROL SCHEDULE

LOCATION	QUANTITY
	TON
	STA. 398+59 TO STA. 401+88.20 RT.
STA. 402+64.20 TO STA. 403+91.5 RT.	24
STA. 399+59 TO STA. 401+88.20 LT.	47
STA. 402+64.20 TO STA. 405+91 LT.	67
TOTAL	205

WIDENING SCHEDULE

LOCATION	HMA BASE COURSE WIDENING, 8"	EARTH EXCAVATION (WIDENING)
	SQ. YD.	CU. YD.
	STAGE I	
STA. 398+60 TO STA. 401+86 RT.	145	33
STA. 402+64 TO STA. 405+80 RT.	141	32
TOTAL	286	65

TOPSOIL SCHEDULE

LOCATION	TOPSOIL FURNISH AND PLACE, 4"
	SQ. YD.
	STA. 398+50 TO STA. 401+88.20
STA. 402+64.20 TO STA. 404+00	168
TOTAL	593

USER NAME = *USER*	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = *SCALE*	CHECKED -	REVISED -
PLOT DATE = *DATE*	DATE -	REVISED -



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907

QUANTITY SCHEDULES

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
574	12BR-1	FULTON	62	14
CONTRACT NO. 68732				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				