	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L25E ACF ROADWAY F. A. P. 67 80% FEDERAL 20% STATE CONSTRUCTION TYPE CODE 0005	LS3E ACHSIP ROADWAY F. A. P. 67 90% FEDERAL 10% STATE CONSTRUCTION TYPE CODE 0021
*	82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	10	10	
*	82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240 VOLT, 60 AMP	EACH	1	1	
*	83003600	LIGHT POLE, ALUMINUM, 45' M. H., 15' DAVIT ARM	EACH	10	10	
	83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8"x6'	EACH	10	10	
*	83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	40	40	
	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	6752	6752	
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	35	35	
*	66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	

* SPECIALTY ITEM

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL. Design Firm
No. 184-001907

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 5 OF 5 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	3 (N), L, RS-3	CASS	64	7
		CONTRACT NO. 72D75		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		