

HMA SURFACE REMOVAL		
LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL, VARIABLE DEPTH
	SQ. YD.	SQ. YD.
STA. 1075+00 TO STA. 1075+15	40	40
STA. 1075+15 TO STA. 18+55		6672
STA. 18+55 TO STA. 18+70	40	40
STA. 1082+27.55 LT. (FULTON LANE)	240	
STA. 1082+27.55 RT. (BUCHANAN STREET)	15	
STA. 1087+39.93 RT. (FREMONT STREET)	121	
TOTAL	456	6752

PERMANENT SEEDING					
LOCATION	SEEDING CLASS 2	NITROGEN FERT. NUT.	PHOSPHORUS FERT. NUT.	POTASSIUM FERT. NUT.	MULCH METHOD 2
	ACRE	POUND	POUND	POUND	ACRE
STA. 1075+00 TO STA. 18+70 LT.	0.5	45	45	45	0.5
STA. 1075+00 TO STA. 18+70 RT.	0.7	63	63	63	0.7
TOTAL	1.2	108	108	108	1.2

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	QUANTITY
	SO FT
SHORT-TERM PAVEMENT MARKING	169
TOTAL	169

HMA SHOULDERS		
LOCATION	HMA SHOULDERS, 8"	HMA SHOULDERS
	SQ. YD.	TON
STA. 1075+00 TO STA. 1075+95.16 LT.		18
STA. 1075+95.16 TO STA. 1082+37.4 LT.	401	
STA. 1082+58 TO STA. 1087+12.20 LT.	218	
STA. 1087+63.6 TO STA. 1095+51.29 LT.	445	
STA. 1095+51.29 TO STA. 1098+75 LT.		26
STA. 1098+75 TO STA. 18+70 LT.	70	
STA. 1075+00 TO STA. 1075+95.16 RT.		24
STA. 1075+95.16 TO STA. 1082+04.3 RT.	378	
STA. 1082+25.4 TO STA. 1086+82.7 RT.	240	
STA. 1087+10.7 TO STA. 1095+51.29 RT.	488	
STA. 1095+51.29 TO STA. 1099+00 RT.		24
STA. 1099+00 TO STA. 18+70 RT.	59	
TOTAL	2299	92

EARTHWORK				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 1075+00 TO STA. 18+70	950	713	340	+373
TOTAL	950	713	340	+373

PAVED SHOULDER REMOVAL	
LOCATION	QUANTITY
	SQ. YD.
STA. 1075+95.16 TO STA. 1082+04 LT.	671
STA. 1082+94 TO STA. 1086+99 LT.	426
STA. 1087+80 TO STA. 1095+51.29 LT.	871
STA. 1075+95.16 TO STA. 1081+81 RT.	722
STA. 1082+56 TO STA. 1086+83 RT.	511
STA. 1087+11 TO STA. 1095+51.29 RT.	911
STA. 1098+75 TO STA. 18+70 LT.	42
STA. 1099+00 TO STA. 18+70 RT.	40
TOTAL	4194

AGGREGATE SHOULDERS, TYPE B	
LOCATION	QUANTITY
	TON
STA. 1075+00 TO STA. 1081+92.4 LT.	53
STA. 1082+93.6 TO STA. 1087+12.2 LT.	45
STA. 1087+63.3 TO STA. 18+70 LT.	117
STA. 1075+00 TO STA. 1081+77.2 RT.	51
STA. 1082+55.5 TO STA. 1086+63.2 RT.	31
STA. 1087+89 TO STA. 18+70 RT.	119
TOTAL	416

HMA BASE COURSE, 11"	
LOCATION	QUANTITY
	SQ. YD.
STA. 1075+95.16 TO STA. 1095+51.29 LT.	1110
STA. 1075+95.16 TO STA. 1086+68 RT.	620
STA. 1087+91 TO STA. 1095+51.29 RT.	412
BUCHANAN STREET	36
FULTON LANE	50
TOTAL	2228

TEMPORARY RAMP	
LOCATION	QUANTITY
	SQ. YD.
STA. 1075+00 TO STA. 1075+05	14
STA. 18+65 TO STA. 18+70	14
STA. 1082+27.55 LT. (FULTON LANE)	12
STA. 1082+27.55 RT. (BUCHANAN STREET)	13
STA. 1087+39.93 RT. (FREMONT STREET)	18
TOTAL	71

PAVEMENT REMOVAL	
LOCATION	QUANTITY
	SQ. YD.
STA. 1081+81 TO STA. 1082+56 RT.	60
STA. 1082+04 TO STA. 1082+94 LT.	71
TOTAL	131

SUB-BASE GRANULAR MATERIAL, TYPE B 4"	
LOCATION	QUANTITY
	SQ. YD.
STA. 1075+95.16 TO STA. 1095+51.29 LT.	1325
STA. 1075+95.16 TO STA. 1086+68 RT.	740
STA. 1087+91 TO STA. 1095+51.29 RT.	497
BUCHANAN STREET	33
FULTON LANE	45
TOTAL	2640

LEVELING BINDER (MACHINE METHOD), N70	
LOCATION	QUANTITY
	TON
STA. 1075+30 TO STA. 18+40	390
TOTAL	390

PRIME COAT		
LOCATION	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)
	TON	TON
STA. 1075+30 TO STA. 18+40	3.5	18.4
STA. 1075+00 TO STA. 18+70	3.5	18.4
STA. 1082+27.55 LT. (FULTON LANE)	0.2	1.1
STA. 1082+27.55 RT. (BUCHANAN STREET)	0.2	1.1
STA. 1087+39.93 RT. (FREMONT STREET)	0.4	2.2
TOTAL	7.8	41.2

INCIDENTAL HOT-MIX ASPHALT SURFACING	
LOCATION	TON
	BUCHANAN STREET
FULTON LANE	26
FREMONT STREET	96
TOTAL	180

DRIVEWAY PAVEMENT REMOVAL	
LOCATION	QUANTITY
	SQ. YD.
STA. 1086+99 TO STA. 1087+80 LT.	107
TOTAL	107

HMA SURFACE COURSE, MIX "D", N70	
LOCATION	QUANTITY
	TON
STA. 1075+00 TO STA. 18+70	754
TOTAL	754

PAVEMENT PATCHING, TYPE II, 12"	
LOCATION	QUANTITY
	SQ YD
STA. 1075+00 TO STA. 18+70	100
TOTAL	100