

AGGREGATE FOR TEMPORARY ACCESS	
LOCATION	QUANTITY
	TON
STA. 1084+22.3 LT. - F.E.	5
STA. 1087+37.5 LT. - C.E.	10
STA. 1093+26.7 LT. - F.E.	5
STA. 1093+31.2 RT. - F.E.	5
TOTAL	25

MODIFIED URETHANE PAVEMENT MARKING - LINE 12"		
LOCATION	SOLID YELLOW	FOOT
STA. 1076+36 TO STA. 1080+14 (MEDIAN)	90	
STA. 1090+46 TO STA. 1094+69 (MEDIAN)	98	
TOTAL	188	

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	QUANTITY
	EACH
STA. 1075+00 TO STA. 18+70	32
TOTAL	32

SHORT-TERM PAVEMENT MARKING	
LOCATION	QUANTITY
	FOOT
STA. 1075+00 TO 18+70	507
TOTAL	507

MODIFIED URETHANE PAVEMENT MARKING - LINE 5"			
LOCATION	SOLID YELLOW	SKIP-DASH (10' / 30')	SOLID WHITE
	FOOT	FOOT	FOOT
STA. 1072+95.40 TO STA. 1075+95.40 EB NPZ	300		
STA. 1075+00 TO STA. 1075+95.40		30	
STA. 1075+95.4 TO STA. 1076+30.4	70		
STA. 1076+30.4 TO STA. 1080+54.4	1696		
STA. 1080+54.4 TO STA. 1081+90	272		
STA. 1082+61 TO STA. 1086+61	800		
STA. 1087+66 TO STA. 1090+39	546		
STA. 1090+39 TO STA. 1095+16	1908		
STA. 1095+16 TO STA. 1095+51	70		
STA. 1095+51 TO STA. 1098+51 WB NPZ	300		
STA. 1095+51 TO STA. 18+70		120	
STA. 1075+00 TO STA. 1081+79 LT. EDGE			679
STA. 1083+07 TO STA. 18+70 LT. EDGE			1726
STA. 1075+00 TO STA. 1081+66 RT. EDGE			666
STA. 1082+67 TO STA. 1086+52 RT. EDGE			385
STA. 1088+07 TO STA. 18+70 RT. EDGE			1226
FREMONT ST LT. EDGE			88
FREMONT ST RT. EDGE			134
SUB-TOTAL	5962	150	4904
TOTAL		11016	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID - LETTERS & SYMBOLS	
LOCATION	QUANTITY
	SQ. FT.
STA. 1084+84 LT. TURN	15.6
STA. 1081+65 LT. TURN	15.6
STA. 1082+85 LT. TURN	15.6
STA. 1083+68 LT. TURN	15.6
STA. 1085+55 LT. TURN	15.6
STA. 1086+35 LT. TURN	15.6
STA. 1087+99 LT. TURN	15.6
STA. 1088+90 LT. TURN	15.6
STA. 1090+05 LT. TURN	15.6
TOTAL	141

RAISED REFLECTIVE PAVEMENT MARKER			
LOCATION	TWO WAY AMBER	ONE WAY AMBER	ONE WAY CRYSTAL
	EACH	EACH	EACH
STA. 1075+25	1		
STA. 1076+30 TO STA. 1080+30		22	
STA. 1080+30 TO STA. 1081+90	8		3
STA. 1082+61 TO STA. 1086+61	22		6
STA. 1087+66 TO STA. 1090+06	7		7
STA. 1090+45 TO STA. 1095+25		26	
STA. 1095+76 TO STA. 18+70	6		
SUB-TOTAL	44	48	16
TOTAL		108	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID - LINE 24"	
LOCATION	SOLID WHITE
	FOOT
STA. 0+46 (BUCHANAN STREET)	12
STA. 0+45 (FULTON LANE)	15
STA. 0+43 (FREMONT STREET)	24
TOTAL	51

SIGN PANEL			
LOCATION	SIGN PANEL - TYPE 1	RELOCATE SIGN PANEL ASSEMBLY - TYPE B	TELESCOPING STEEL SIGN SUPPORT
	SQ. FT.	EACH	FOOT
STA. 1074+05, RT.	8.5		14.0
STA. 1075+95, RT.	5.0		12.5
STA. 1079+00, RT.	4.0		12.0
FULTON LANE	9.0		13.0
BUCHANAN STREET	9.0		13.0
STA. 1083+60, RT.	4.0		12.0
STA. 1085+35, LT.	4.0		12.0
FREMONT STREET	9.0		13.0
STA. 1092+40, LT.	4.0		12.0
STA. 1095+45, LT.	5.0		12.5
STA. 1098+00, LT.		1	15.0
TOTAL	61.5	1	141.0

MODIFIED URETHANE PAVEMENT MARKING - LINE 6"		
LOCATION	SOLID WHITE	SKIP-DASH (2' / 6')
	FOOT	FOOT
STA. 1078+95.4 TO STA. 1080+75.4 RT.		138
STA. 1080+75.4 TO STA. 1081+90 RT.	115	
STA. 1082+61 TO STA. 1083+76.28	115	
STA. 1083+76.28 TO STA. 1085+46.47 LT. & RT.		264
STA. 1085+46.47 TO STA. 1086+61 RT.	115	
STA. 1087+66 TO STA. 1090+11 LT.	245	
STA. 1090+11 TO STA. 1092+51 LT.		180
SUB-TOTAL	590	582
TOTAL		1172

THERMOPLASTIC PAVEMENT MARKING - LINE 5"	
LOCATION	SOLID YELLOW
	FOOT
STA. 0+46 TO STA. 0+66 (BUCHANAN STREET)	40
STA. 0+46 TO STA. 0+88 (FULTON LANE)	86
STA. 0+43 TO STA. 1+01 (FREMONT STREET)	116
TOTAL	242

STRIP REFLECTIVE CRACK CONTROL TREATMENT	
LOCATION	QUANTITY
	FOOT
STA. 1075+95.16 TO STA. 1095+51 LT.	1956
STA. 1075+95.16 TO STA. 1086+68 RT.	1073
STA. 1087+91 TO STA. 1095+51 RT.	760
TOTAL	3789

PIPE CULVERT			
LOCATION	PIPE CULVERT CLASS D TYPE 1, 15"	METAL END SECTIONS, 15"	PIPE CULVERT REMOVAL
	FOOT	EACH	FOOT
STA. 1093+04 LT.		1	
STA. 1093+04 TO STA. 1093+48 LT.	44		38
STA. 1093+48 LT.		1	
STA. 1093+11 RT.		1	
STA. 1093+11 TO STA. 1093+51 RT.	40		30
STA. 1093+51 RT.		1	
TOTAL	84	4	68