

LIGHTING								
LOCATION	ELECTRIC SERVICE INSTALLATION	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	UNIT DUCT, 600V, 2-1C NO. 8 GROUND, (XLP-TYPE), 3/4" DIA. POLYETHYLENE	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT 250 WATT	LIGHTING CONTROLLER POLE MOUNTED 240 VOLT, 60 AMP	LIGHT POLE, ALUMINIUM, 45' M. H., 15' DAVIT ARM	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN
	EACH	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH
STA. 1078+45 TO STA. 1090+96.99			2907					
STA. 1081+23		52						
STA. 0+46 (FULTON LANE)		41						
STA. 1082+95		52						
STA. 1084+22.3 (F. E.)		34						
STA. 0+79 (FREEMONT STREET)		51						
STA. 1087+37.5 (C. E.)		41						
STA. 1082+95	1				1			
STA. 1078+45				1		1	1	4
STA. 1080+03				1		1	1	4
STA. 1081+63				1		1	1	4
STA. 1082+59				1		1	1	4
STA. 1083+92				1		1	1	4
STA. 1085+25				1		1	1	4
STA. 1086+58				1		1	1	4
STA. 1087+77				1		1	1	4
STA. 1089+37				1		1	1	4
STA. 1090+96.99				1		1	1	4
TOTAL	1	271	2907	10	1	10	10	40

STONE RIPRAP, CLASS B3	
LOCATION	QUANTITY
	TON
STA. 1083+70.1 TO STA. 1083+83.3 RT	5
STA. 1083+84.7 TO STA. 1083+98.3 LT	5
TOTAL	10