

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	100% State
			0014
			TOTAL QTY
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5
70106500	TEMPORARY BRIDGE TRAFFIC SIGNAL	EACH	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	8
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1050
70300100	SHORT TERM PAVEMENT MARKING	FOOT	97
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	32
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1050
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	1263
78300100	PAVEMENT MARKING REMOVAL	SQ FT	738
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	10
Z0041895	POLYMER CONCRETE	CU FT	3.0
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	3
Z0012130	BRIDGE DECK SCARIFICATION, 3/4"	SQ YD	2486
Z0012164	BRIDGE DECK MICROSILICA CONCRETE OVERLAY, 2-1/2"	SQ YD	2486
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	121
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2
* Z0030332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE NARROW), TEST LEVEL 3	EACH	2

* SPECIALTY ITEM

QUANTITIES
FAP 608 (IL 111)
SECTION (126)I-1
MACOUPIN COUNTY