

TREE REMOVAL - EASTBOUND

STATION	TREE REMOVAL (6 TO 15 UNITS) (UNIT)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT)	STATION	TREE REMOVAL (6 TO 15 UNITS) (UNIT)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT)
300+67		16	413+40	14	
336+13	12		413+90	13	
339+25	10		414+40		17
339+33	6		414+88	15	
339+39	7		423+35	19	
339+48	7		471+85	10	
341+20	26		474+19	14	
341+85	15		474+86	7	
346+70		20	475+69	15	
390+83	19		479+94	13	
391+16		17	483+32	13	
391+50	29		483+42	13	
392+27	36		483+44	6	
392+27	7		483+47	7	
392+62		20	483+50	6	
392+93		25	483+75	13	
393+16	10		495+15	14	
393+30	13		497+66	26	
403+34	11		503+71	11	
403+50		17	511+46	15	
403+95		16	512+22	21	
404+50		22	518+85	6	
405+00		23	520+34	8	
405+48		23	522+29	9	
406+45		22	523+76		19
407+00	28		538+38	21	
407+00		24	538+99	9	
407+50		18	538+99		22
408+50		19	539+37	11	
408+95		18	550+77		16
409+50		16	554+67	15	
409+95		18	601+72	12	
410+44	15		602+74	18	
411+00	22		603+69	18	
411+44	18		606+90		21
411+92	14		611+93	15	
412+40	15		613+16		22
412+90	14		TOTALS	741	451

TREE REMOVAL - WESTBOUND

STATION	TREE REMOVAL (6 TO 15 UNITS) (UNIT)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT)	STATION	TREE REMOVAL (6 TO 15 UNITS) (UNIT)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT)
313+09	6		343+37		36
318+42		16	344+36	51	
323+25		30	344+88	27	
323+76		29	345+37	48	
325+79		38	345+37		18
326+30	24		345+85	23	
326+30	10		346+30	51	
326+30		22	346+30		18
326+55		39	346+85	61	
327+80	13		367+70	8	
328+80	23		368+71	60	
328+80		23	369+20	24	
329+77	35		369+20		36
329+77		38	369+70		22
330+29	33		370+19		37
330+29		20	370+68		24
330+50	18		371+08	32	
330+50		28	376+70	8	
330+68	9		388+71		19
331+85	9		389+51		20
332+02	49		389+83		22
332+02		52	395+64		16
332+56	26		438+24		24
332+56		36	438+75		23
336+45	23		439+26		18
336+45		26	439+75		43
337+49	41		440+23		38
337+49		17	441+23		39
338+94	38		441+75	14	
338+94		40	447+18	10	
339+45	77		447+18		18
340+43	68		447+69	30	
341+04	27		465+99	56	
341+60	44		466+48	20	
341+91	15		466+95	44	
341+91		16	467+44	30	
342+90	44		467+44		23
342+90		17	467+95	36	

STATION	TREE REMOVAL (6 TO 15 UNITS) (UNIT)	TREE REMOVAL (OVER 15 UNITS DIAMETER) (UNIT)
467+95		16
468+96	52	
469+42	74	
469+95	80	
470+90	10	
470+90		29
471+35		38
471+88	36	
472+39		100
472+58	23	
532+27		20
544+00		16
545+06		24
545+59		26
546+95		17
548+13		22
575+45	15	
575+93	30	
576+02	30	
598+75	6	
545+95		18
TOTALS	1621	1307

TREE REMOVAL, ACRES - EASTBOUND

STATION	TO	STATION	LENGTH (FEET)	WIDTH (FEET)	QUANTITY (ACRES)
342+37	TO	346+70	433	20	0.20
394+30	TO	396+40	210	20	0.10
491+25	TO	494+76	351	20	0.16
510+20	TO	510+80	60	14	0.02
512+50	TO	512+76	26	12	0.01
513+10	TO	513+58	48	10	0.01
524+16	TO	525+56	140	20	0.06
615+20	TO	618+00	280	21	0.13
TOTAL					0.75

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ct:\pw\work\p\dot\teasleyck\d0148656\07	4416-sht-sch.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 8/17/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TREE REMOVAL
SCHEDULE

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(18-47,48,48R)	Cumberland	30	10
CONTRACT NO. 74416			ILLINOIS FED. AID PROJECT	