

GUARDRAIL REMOVAL

DESCRIPTION	STATIONING		SIDE	LENGTH (FOOT)
	FROM	TO		
EASTBOUND				
OVERHEAD SN 018-0038	344+20	348+50	RT	430
OVERHEAD SN 018-0016	429+88	434+18	RT	430
BRIDGE SN 018-0052	483+09	486+44	RT	335
BRIDGE SN 018-0052	484+84	486+44	LT	160
OVERHEAD SN 018-0039	525+26	529+56	RT	430
OVERHEAD SN 018-0083	617+05	621+35	RT	430
EASTBOUND TOTAL				2215
WESTBOUND				
OVERHEAD SN 018-0038	349+00	353+30	LT	430
OVERHEAD SN 018-0016	434+68	438+98	LT	430
BRIDGE SN 018-0051	487+96	489+56	LT	160
BRIDGE SN 018-0051	487+96	491+04	RT	308
OVERHEAD SN 018-0039	525+26	529+56	LT	343
OVERHEAD SN 018-0053	621+49	625+79	LT	430
WESTBOUND TOTAL				2101
TOTAL				4316

GUARDRAIL SCHEDULE

DESCRIPTION	STATIONING		SIDE	(FOOT)	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 6B	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
	FROM	TO								
EASTBOUND										
OVERHEAD SN 018-0038	345+94.5	346+44.5	RT							1
	346+44.5	348+07.0	RT	162.5					3	
	348+07.0	348+63.0	RT					1	1	
OVERHEAD SN 018-0016	431+62.5	432+12.5	RT							1
	432+12.5	433+75.0	RT	162.5					3	
	433+75.0	434+31.0	RT					1	1	
BRIDGE SN 018-0052	483+50.0	484+00.0	LT							1
	484+00.0	486+00.0	LT	200					3	
	486+00.0	486+44.0	LT			1			1	
	483+87.5	484+37.5	RT							1
	484+37.5	486+00.0	RT	162.5					3	
	486+00.0	486+44.0	RT				1		1	
OVERHEAD SN 018-0039	527+00.5	527+50.5	RT							1
	527+50.5	529+13.0	RT	162.5					3	
	529+13.0	529+69.0	RT					1	1	
OVERHEAD SN 018-0053	618+79.5	619+29.5	RT							1
	619+29.5	620+92.0	RT	162.5					3	
	620+92.0	621+48.0	RT					1	1	
EASTBOUND TOTALS				1012.5	6	2	4	24	6	
WESTBOUND										
OVERHEAD SN 018-0038	348+87.0	349+43.0	LT						1	1
	349+43.0	351+05.5	LT	162.5					3	
	351+05.5	351+55.5	LT							1
OVERHEAD SN 018-0016	434+55.0	435+11.0	LT					1	1	
	435+11.0	436+73.5	LT	162.5					3	
	436+73.5	437+23.5	LT							1
BRIDGE SN 018-0051	487+96.0	488+40.0	LT							1
	488+40.0	490+02.5	LT	162.5				1	3	
	490+02.5	490+52.5	LT							1
	487+96.0	488+40.0	RT						1	
	488+40.0	490+40.0	RT	200					3	
	490+40.0	490+90.0	RT							1
OVERHEAD SN 018-0039	529+93.0	530+49.0	LT						1	1
	530+49.0	532+11.5	LT	162.5					3	
	532+11.5	532+61.5	LT							1
OVERHEAD SN 018-0053	621+36.0	621+92.0	LT						1	1
	621+92.0	623+54.5	LT	162.5					3	
	623+54.5	624+04.5	LT							1
WESTBOUND TOTAL				1012.5	6	2	4	24	6	
TOTAL				2025	12	4	8	48	12	

PIER PROTECTION SCHEDULE

STATION	OVERHEAD S.N.	SAND MODULE IMPACT ATTENUATOR TO BE REMOVED (EACH)	IMPACT ATTENUATORS (NON-REDIRECTIVE) TEST LEVEL 3 (EACH)
348+75	018-0038	2	2
433+00	018-0016	2	2
529+81	018-0039	2	2
621+42	018-0053	2	2
TOTALS		8	8

PIPE UNDERDRAINS SCHEDULE

STATION	LENGTH (FEET)	PIPE UNDERDRAINS 6" (FEET)	PIPE UNDERDRAINS 6" (SPECIAL) (FEET)	CLEANING UNDERDRAIN OUTLETS (EACH)	CONCRETE HEADWALL REMOVAL SPECIAL (EACH)	SHOULDER REMOVAL AND REPLACEMENT 12 1/2" (FEET)
EASTBOUND						
292+20	482+93	19073	38146	1820	76	20881
482+93	489+50	657				
489+50	673+00	18350	36700	1820	76	20338
EASTBOUND TOTALS		74846	3640	0	152	41219
WESTBOUND						
292+20	346+38	5418		22		0
346+38	351+38	500	1000	48	2	1016
351+38	432+05	8067		32		0
432+05	437+05	500	1000	48	2	1016
437+05	457+80	2075		8		0
457+80	482+93	2513	5026	288	12	2373
482+93	489+50	657				0
489+50	673+00	18350	36700	1772	82	20338
WESTBOUND TOTALS		43726	2156	62	98	24743
TOTALS		118572	5796	62	250	65962