

PRE-STAGE I QUANTITIES

STATION TO STATION	LENGTH (FEET)	PAVEMENT MARKING REMOVAL (SQ FT)	PAVED SHOULDER REMOVAL (SQ YD)	HMA SHOULDERS, 13" (SQ YD)
EASTBOUND				
284+70 TO 344+62	5992	1997	2663	2663
344+62 TO 352+62	800	267	356	356
352+62 TO 430+30	7768	2589	3452	3452
430+30 TO 438+30	800	267	356	356
438+30 TO 486+23	4793	1598	2130	2130
486+23 TO 488+17	194	145	0	0
488+17 TO 525+68	3751	1250	1667	1667
525+68 TO 533+68	800	267	356	356
533+68 TO 617+42	8374	2791	3722	3722
617+42 TO 625+42	800	267	356	356
625+42 TO 677+24	5182	1671	2303	2303
TOTALS		13109	17361	17361
WESTBOUND				
345+38 TO 358+88	1350	417	367	367
431+05 TO 444+55	1350	417	367	367
452+80 TO 486+23	3343	948	1486	1486
486+23 TO 488+17	194	145	0	0
488+17 TO 525+94	3777	1259	1678	1678
525+94 TO 533+94	800	267	356	356
533+94 TO 617+42	8348	2782	3710	3710
617+42 TO 625+42	800	267	356	356
625+42 TO 683+04	5762	1920	2561	2561
TOTALS		8422	10881	10881

STAGE I QUANTITIES

STATION TO STATION	LENGTH (FEET)	PAVED SHOULDER REMOVAL (SQ YD)	HMA SHOULDERS, 10" (SQ YD)	HMA SHOULDERS, 13" (SQ YD)
EASTBOUND				
277+20 TO 344+62	6742	3995	3995	0
344+62 TO 352+62	800	533	0	533
352+62 TO 430+30	7768	5179	5179	0
430+30 TO 438+30	800	533	0	533
438+30 TO 486+23	4793	3195	3195	0
486+23 TO 488+17	194	0	0	0
488+17 TO 525+68	3751	2501	2501	0
525+68 TO 533+68	800	533	0	533
533+68 TO 617+42	8374	5583	5583	0
617+42 TO 625+42	800	533	0	533
625+42 TO 680+54	5512	3455	3455	0
TOTALS		26040	23908	2132
WESTBOUND				
345+38 TO 353+63	825	550	0	550
431+05 TO 439+30	825	550	0	550
452+80 TO 486+23	3343	2228	2228	0
486+23 TO 488+17	194	0	0	0
488+17 TO 525+94	3777	2518	2518	0
525+94 TO 533+94	800	533	0	533
533+94 TO 617+42	8348	5565	5565	0
617+42 TO 625+42	800	533	0	533
625+42 TO 690+54	6512	3841	3841	0
TOTALS		16318	14152	2166

STAGE II QUANTITIES

STATION TO STATION	LENGTH (FEET)	RELOCATE TEMPORARY CONCRETE BARRIER (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
EASTBOUND			
342+37 TO 352+62	1025		1
428+05 TO 438+30	1025		1
523+43 TO 533+68	1025		1
615+17 TO 625+42	1025		1
TOTALS	4100		4
WESTBOUND			
346+38 TO 353+63	725		1
432+05 TO 439+30	725		1
525+94 TO 536+19	1025		1
617+42 TO 627+67	1025		1
TOTALS	3500		4