

90% FED  
10% STATE

90% FED  
10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SN 018-0045 SN 018-0046 0004	SN 018-0047 SN 018-0048 0014	SN 018-0049 SN 018-0050 0014
50200100	STRUCTURE EXCAVATION	CU YD	648	393	255	
50300225	CONCRETE STRUCTURES	CU YD	202.7	104.6	98.1	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	2734.7	687.4	2047.3	
50300260	BRIDGE DECK GROOVING	SO YD	7200	1711	5489	
50300300	PROTECTIVE COAT	SO YD	16029	2048	13981	
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4320	4320		
50500505	STUD SHEAR CONNECTORS	EACH	23895	7047	16848	
50800105	REINFORCEMENT BARS	POUND	176402	176402		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	620290	730	162440	
50800515	BAR SPLICERS	EACH	336	180	156	
51100100	SLOPE WALL 4 INCH	SO YD	108	108		
51100300	SLOPE WALL 6 INCH	SO YD	27		27	
51500100	NAME PLATES	EACH	4	2	2	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		SN 018-0045 SN 018-0046 0004	SN 018-0047 SN 018-0048 0014	SN 018-0049 SN 018-0050 0014
52000110	PREFORMED JOINT STRIP SEAL	FOOT			152	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH		35		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH			48	
52100505	ANCHOR BOLTS, 5/8"	EACH			192	
52100520	ANCHOR BOLTS, 1"	EACH		84		
54003000	CONCRETE BOX CULVERTS	CU YD	595	595		
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	40	40		
58700300	CONCRETE SEALER	SO FT			1359	
59100100	GEOCOMPOSITE WALL DRAIN	SO YD		231	115	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	536	536		
60100905	PIPE DRAINS 4"	FOOT		500	540	
60107700	PIPE UNDERDRAINS 6"	FOOT	864	864		
60108200	PIPE UNDERDRAINS 6" (SPECIAL)	FOOT	80	80		

FILE NAME :	USER NAME : steffanek	DESIGNED -	REVISED -
c:\pwwork\pwwork\steffanek\d0186453.dwg	4466-shrtaoq.dgn	DRAWN -	REVISED -
	PLOT SCALE : 180.0000 ' = 1 in.	CHECKED -	REVISED -
	PLOT DATE : 8/28/2012	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NA SHEET NO. 3 OF 6 SHEETS STA. TO STA.

• (18-47-VBK,18-47B,18-47H)BR

P.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	*	CUMBERLAND	147	6
			CONTRACT NO. 74466	
ILLINOIS FED. AID PROJECT				